

FLOOD INSURANCE STUDY



MARATHON COUNTY, WISCONSIN AND INCORPORATED AREAS

Abbotsford, City of	550299
Athens, Village of	550246
*Birnamwood, Village of	550413
Brokaw, Village of	550247
Colby, City of	550049
*Dorchester, Village of	550241
Edgar, Village of	550248
Elderon, Village of	550249
Fenwood, Village of	550250
Hatley, Village of	550251
Kronenwetter, Village of	550193
Marathon City, Village of	550252
Marathon County (Unincorporated Areas)	550245
*Marshfield, City of	550515
Mosinee, City of	555567
Rothschild, Village of	555577
Schofield, City of	555579
*Spencer, Village of	550315
Stratford, Village of	550256
*Unity, Village of	550257
Wausau, City of	550258
Weston, Village of	550323



*No Special Flood Hazard Areas Identified

PRELIMINARY
12/01/2016



Federal Emergency Management Agency
FLOOD INSURANCE STUDY NUMBER
55073CV000B

Marathon County, Wisconsin
and Incorporated Areas

**NOTICE TO
FLOOD INSURANCE STUDY USERS**

Communities participating in the National Flood Insurance Program have established repositories of flood hazard data for floodplain management and flood insurance purposes. This Flood Insurance Study (FIS) may not contain all data available within the repository. It is advisable to contact the community repository for any additional data.

The Federal Emergency Management Agency (FEMA) may revise and republish part or all of this effective FIS report at any time. In addition, FEMA may revise part of this FIS report by the Letter of Map Revision (LOMR) process, which does not involve republication or redistribution of the FIS report. Therefore, users should consult community officials and check the Community Map Repository to obtain the most current FIS components.

Selected Flood Insurance Rate Map panels for this community contain information that was previously shown separately on the corresponding Flood Boundary and Floodway Map panels (e.g., floodways and cross sections). In addition, former flood hazard zone designations have been changed as follows.

<u>Old Zone(s)</u>	<u>New Zone</u>
A1 through A30	AE
B	X
C	X

Initial Countywide FIS Effective Date: July 22, 2010

Revised Effective Date: To Be Determined

TABLE OF CONTENTS

1.0	INTRODUCTION	1
	1.1 Purpose of Study	1
	1.2 Authority and Acknowledgment	1
	1.3 Coordination	3
2.0	AREA STUDIED	4
	2.1 Scope of Study	4
	2.2 Community Description	6
	2.3 Principal Flood Problems	7
	2.4 Flood Protection Measures	8
3.0	ENGINEERING METHODS	9
	3.1 Hydrologic Analyses	9
	3.2 Hydraulic Analyses	14
	3.3 Vertical Datum	17
4.0	FLOOD PLAIN MANAGEMENT APPLICATIONS	18
	4.1 Floodplain Boundaries	18
	4.2 Floodways	19
5.0	INSURANCE APPLICATIONS	35
6.0	FLOOD INSURANCE RATE MAP	36
7.0	OTHER STUDIES	40
8.0	LOCATION OF DATA	40
9.0	BIBLIOGRAPHY AND REFERENCES	40
10.0	ADDITIONAL INFORMATION	44
	10.1 FIRM Notes to Users	44

TABLE OF CONTENTS *(Continued)*

FIGURES

FIGURE 1 – FREQUENCY – DISCHARGE, DRAINAGE AREA CURVE	12
FIGURE 2 – FLOODWAY SCHEMATIC	35
FIGURE 3 – FIRM NOTES TO USERS	44
FIGURE 4 – MAP LEGEND FOR FIRM	46

TABLES

TABLE 1 – INITIAL AND FINAL CCO MEETINGS	4
TABLE 2 – FLOODING SOURCES STUDIED BY DETAILED METHODS	4
TABLE 3 – PREVIOUSLY INCORPORATED LOMR _s	5
TABLE 4 – LETTERS OF MAP CHANGE INCORPORATED IN THIS FIS	5
TABLE 5 – SUMMARY OF DISCHARGES	13
TABLE 6 – MANNING'S “n” VALUES	17
TABLE 7 – FLOODWAY DATA	21
TABLE 8 – COMMUNITY MAP HISTORY	37

EXHIBITS

Exhibit 1 -	Flood Profiles		
	Big Rib River	Panels	01P-04P
	Black Creek	Panel	05P
	Bull Junior Creek	Panels	06P-10P
	Eau Claire River	Panels	11P-14P
	Jim Moore Creek	Panel	15P
	Johnson Creek	Panels	16P-18P
	Little Rib River	Panel	19P
	Potato Creek	Panel	20P
	Wisconsin River	Panels	21P-27P
	Wisconsin River East Channel	Panels	28P
Exhibit 2 -	Flood Insurance Rate Map Index		
	Flood Insurance Rate Map		

**FLOOD INSURANCE STUDY
MARATHON COUNTY, WISCONSIN AND INCORPORATED AREAS**

1.0 INTRODUCTION

1.1 Purpose of Study

This countywide Flood Insurance Study (FIS) revises and updates information on the existence and severity of flood hazards in the geographic area of Marathon County, including the cities of Abbotsford, Colby, Marshfield, Mosinee, Schofield, and Wausau; the villages of Athens, Birnamwood, Brokaw, Dorchester, Edgar, Elderon, Fenwood, Hatley, Kronenwetter, Marathon City, Rothschild, Spencer, Stratford, Unity, and Weston; and the unincorporated areas of Marathon County (referred to collectively herein as Marathon County). Note that the cities of Abbotsford, Colby, Marshfield, Mosinee, and Schofield, and the villages of Birnamwood, Brokaw, Dorchester, Edgar, Elderon, Fenwood, Hatley, Kronenwetter, Rothschild, Spencer, Stratford, and Weston did not have previous FIS text. Within the geographic area of Marathon County, no Special Flood Hazard Areas have been identified for the City of Marshfield and the villages of Birnamwood, Dorchester, Spencer, and Unity.

The flood-hazard information for the portions of the cities of Abbotsford, Colby, Marshfield, and Unity, and the villages of Birnamwood and Dorchester that lie in Marathon County are included in this FIS report. For flood-hazard information in Clark, Shawano, and Wood Counties, see separately published FIS reports and Flood Insurance Rate Maps (FIRM).

This FIS aids in the administration of the National Flood Insurance Act of 1968 and the Flood Disaster Protection Act of 1973. This FIS has developed flood risk data for various areas of the county that will be used to establish actuarial flood insurance rates. This information will also be used by the communities of Marathon County to update existing floodplain regulations as part of the Regular Phase of the National Flood Insurance Program (NFIP), and will also be used by local and regional planners to further promote sound land use and floodplain development. Minimum floodplain management requirements for participation in the NFIP are set forth in the Code of Federal Regulations at 44 CFR, 60.3.

In some States or communities, floodplain management criteria or regulations may exist that are more restrictive or comprehensive than the minimum Federal requirements. In such cases, the more restrictive criteria take precedence, and the State (or other jurisdictional agency) will be able to explain them.

1.2 Authority and Acknowledgments

The sources of authority for this FIS report are the National Flood Insurance Act of 1968 and the Flood Disaster Protection Act of 1973.

This FIS was prepared to include the unincorporated areas of, and incorporated communities within, Marathon County in a countywide format. Information on the authority and acknowledgements for each jurisdiction included in this countywide FIS, as compiled from their previously printed FIS reports, is shown below:

Athens, Village of: The hydrologic and hydraulic analyses for this study were performed by the U.S. Geological Survey (USGS) for the Federal Insurance Administration, under Inter-Agency Agreement No. IAA-H-9-77, Project Order No. 25. This work was completed in August 1978.

Marathon County (Unincorporated Areas): The hydrologic and hydraulic analyses for this study were performed by the USGS, for the Federal Insurance Administration, under Inter-Agency Agreement No. IAA-H-17-72. This study was completed in August 1974 and the FIRM from this initial study became effective February 1, 1979. The additional hydrologic and hydraulic analyses for the expanded study were also performed by the USGS, for the Federal Insurance Administration under Inter-Agency Agreement No. IAA-H-9-77. This work, which was completed in April 1979, covered the significant flooding effects of the Big Rib River, Little Rib River, Eau Claire River, Bull Junior Creek, and Johnson Creek, all in the unincorporated areas of Marathon County.

Marathon City, Village of: The hydrologic and hydraulic analyses for this study were performed by the USGS for the Federal Insurance Administration, under Inter-Agency Agreement No. IAA-H-9-77, Project Order No. 25. This work was completed in November 1978.

Wausau, City of: The hydrologic and hydraulic analyses for this study were performed by the USGS for the Federal Insurance Administration, under Inter-Agency Agreement No. IAA-H-3-73, Project Order No. 3. This work was completed in August 1974.

Initial Countywide Analyses

For the previous FIS in 2010, digital conversion and re-delineation of special flood hazard areas was performed by CDM Federal Programs Corporation (CDM), under

contract HSFE05-05-D-0027/006. Work was completed October 19, 2007. The hydrologic and hydraulic analyses for that study were developed by the U.S. Army Corps of Engineers (USACE). The digital base mapping information was provided in digital format by Marathon County. The base mapping information was derived from data compiled in 2005. That data met or exceeded National Mapping Accuracy Standards.

This Physical Map Revision

This countywide FIS incorporates a 316-Physical Map Revision (PMR) that revises the hydrologic and hydraulic analyses for Lake Wausau. The analyses for this study were performed by the Wisconsin Department of Natural Resources for FEMA under Contract No. EMC-2011-CA-7010. The study was complete in January, 2015.

The coordinate system used for the production of the FIRM is Universal Transverse Mercator (UTM) Zone 16, North American Datum of 1983 (NAD 83), GRS 80 spheroid. Differences in the datum and spheroid used in the production of FIRMs for adjacent counties may result in slight positional differences in map features at the county boundaries. These differences do not affect the accuracy of information shown on the FIRM.

1.3 Coordination

An initial Consultation Coordination Officer (CCO) meeting is held typically with representatives of FEMA, the community, and the study contractor to explain the nature and purpose of a FIS and to identify the streams to be studied by detailed methods. A final CCO meeting is held typically with representatives of FEMA, the community, and the study contractor to review the results of the FIS.

The final CCO meeting for this countywide FIS was held on **TBD**, and attended by representatives of FEMA WDNR and community officials to review the results of the study. All problems raised at that meeting have been addressed in this study.

The dates of the initial and final CCO meetings held for previous FIS for jurisdictions within Marathon County are shown in Table 1, "Initial and Final CCO Meetings".

TABLE 1 – INITIAL AND FINAL CCO MEETINGS

<u>Community</u>	<u>Initial CCO Date</u>	<u>Final CCO Date</u>
Village of Athens	March 15, 1977	July 17, 1979
Marathon Co., Unincorporated Areas	June 10, 1976	August 6, 1980
Village of Marathon City	*	July 17, 1979
City of Wausau	*	December 16, 1975

*Information Not Available

For the previous FIS, the initial CCO meeting was held September 19, 2006 and was attended by representatives of CDM, the Wisconsin Department of Natural Resources (WDNR), FEMA, and the communities of Marathon County. The results of the study were reviewed at the final CCO meeting held on February 19, 2009 and attended by representatives of CDM, WDNR, FEMA and the communities. All problems raised at that meeting were addressed in that study.

2.0 AREA STUDIED

2.1 Scope of Study

This FIS report covers the geographic area of Marathon County, Wisconsin, including the incorporated communities listed in Section 1.1. The areas studied by detailed methods were selected with priority given to all known flood hazards and areas of projected development and proposed construction.

All or portions of the flooding sources listed in Table 2, “Flooding Sources Studied by Detailed Methods,” were previously studied by detailed methods. The limits of detailed study are indicated on the Flood Profiles (Exhibit 1) and on the FIRM (Exhibit 2).

TABLE 2 – FLOODING SOURCES STUDIED BY DETAILED METHODS

<u>Stream</u>	<u>Limits of Detailed Study</u>
Big Rib River	From its confluence at the Wisconsin River to State Highway 29.
Black Creek	From approximately 3,000 feet downstream of Degner Street to approximately 3,500 feet upstream of the City of Athens Dam.
Bull Junior Creek	From its confluence at the Mosinee flowage area of the Wisconsin River to approximately 1.9 miles upstream of County Highway X at Town Road.

TABLE 2 – FLOODING SOURCES STUDIED BY DETAILED METHODS
(continued)

<u>Stream</u>	<u>Limits of Detailed Study</u>
Eau Claire River	From the Brooks and Ross Dam to the upstream side of County Highway N.
Jim Moore Creek	From its confluence with the Wisconsin River to approximately 4,300 feet upstream of the Tenth Street bridge.
Johnson Creek	From County Highway C to State Highway 153.
Little Rib River	From its confluence with Big Rib River to Stettin Drive

This countywide FIS also incorporates the FEMA-issued determination Letter of Map Revision (LOMR), Letter of Map Amendment (LOMA), and Special Response (SR), as shown in Table 3, "Letters of Map Change."

TABLE 3 – PREVIOUSLY INCORPORATED LOMRs

<u>Community</u>	<u>Flooding Source(s)/ Project Identifier</u>	<u>Case Number</u>	<u>Date Issued</u>	<u>Type</u>
Wausau, City of	Wisconsin River	98-05-051P	05/05/1999	LOMR

TABLE 4 – LETTER OF MAP CHANGE INCORPORATED IN THIS FIS

<u>Community</u>	<u>Flooding Source(s)/ Project Identifier</u>	<u>Case Number</u>	<u>Date Issued</u>	<u>Type</u>
Marathon County Rothschild, Village of Schofield, City of Wausau, City of	Wisconsin River	15-05-0713P	01/26/2015	LOMR

Previous FIS's studied all or portions of Big Sandy Creek, Bull Junior Creek and Tributary, Cedar Creek, Comet Creek, Eau Claire River, Little Eau Claire River, Plover River, Prospect Creek, Skulen Creek, Spranger Creek, Spring Brook, Trappe River, and numerous unnamed streams by approximate methods.

Approximate analyses were used to study those areas having a low development potential or minimal flood hazards. The Zone A floodplain boundaries for the streams listed above in Marathon County were developed using limited detail study

techniques. The remaining Zone A floodplain boundaries were digitized and adjusted to fit the best available topographic data. The scope and methods of study were proposed to, and agreed upon, by FEMA and the WDNR.

For this revised countywide FIS, LOMR Case #15-05-0713P was incorporated into the DFIRM and FIS as a physical map revision (PMR). The basis of this LOMR was to revise the floodway on the Wisconsin River in the vicinity of Lake Wausau to more closely represent the updated terrain data provided by the county.

2.2 Community Description

Marathon County, located in the central part of Wisconsin, is the largest in area of all Wisconsin counties and covers approximately one million acres. The county, named for the Greek battlefield, witnessed its first settlement in the 1830s. Clockwise from the northeast, surrounding counties are Taylor, Lincoln, Langlade, Shawano, Waupaca, Portage, Wood, and Clark. In 1990 and 2000, the U.S. Bureau of the Census reported the population of the area to be 115,400 and 125,834, respectively (Reference 1).

The climate of the area is classified as continental, with long, relatively cold winters and warm summers. Periods with consecutive days of minimum temperatures below zero are not unusual during the months of December, January, and February. Summers are mostly pleasant, but usually have one or more periods with consecutive days with temperatures of 90 degrees Fahrenheit (°F) or more. Precipitation is ample for the economy of the region. Thunderstorms are the principal source of moisture during the summer. Snowfall is extremely variable from one year to the next.

The Wisconsin River is the chief topographic feature in this section of northern Wisconsin. The land surface is moderately hilly, with a relief of approximately 200 feet. The hills are so moderate in slope that most roads are laid out on the rectangular system of section lines. Several quartzite hills, of which Rib Mountain is the highest, are located in Marathon County. Rib Mountain's peak, which is 1,940 feet, rises approximately 640 feet above the surrounding upland. Few natural lakes exist in the county, but reservoirs have been created along the Wisconsin River and some of its tributaries.

Land uses in the county include agriculture, silviculture, light industry, transportation, public utilities, and parks. Most of the floodplains are in open space uses, that is, cropland, woodland, and pasture. Residential development is scattered throughout the county, with most residences being single-family homes on farmsteads located adjacent to villages and towns, and in unincorporated areas, mostly around the outskirts of Wausau.

Marathon County is credited with 377,800 acres of forest land, but the tree cover is generally light. In the sawtimber category, oak, elm, and hard maple trees lead the list; but, a substantial volume of softwoods also exist. Continuing economic development within the study area is expected. Extensive development is not recommended for flood-prone areas.

2.3 Principal Flood Problems

Overall flooding in Marathon County is generally due to high stages on the Wisconsin River.

In the Village of Athens, flooding on Black Creek and Potato Creek has been minor. In the 1930's, reportedly, a dam located just upstream from State Highway 97 on Black Creek failed in Athens, causing severe flooding downstream (Reference 2). The 1930 flood was at peak stream discharge. It is believed that a log jam caused the dam to fail. The most severe floods for Black Creek and Potato Creek in Athens are caused by rain on frozen ground or intense thunderstorms. These storms are normally limited to relatively small areas or narrow bands along cold fronts and squall lines. Floods that are generally less severe are caused by a combination of melting snow and rainfall in the spring. Stream gaging records account for the effect of snowmelt on flooding.

The greatest recorded flood on the Eau Claire River at Kelly (2.0 miles east of Schofield) occurred August 1926 according to USGS records. This flood's recurrence interval is estimated to be between 25 and 50 years. The period of record is from 1914 to 1926 and from 1940 to the present.

In the Village of Marathon City, the maximum recorded discharge on the Big Rib River at the gaging station at Rib Falls was 23,800 cubic feet per second (cfs) on August 31, 1938. This was approximately a 30-year recurrence interval flood, but did very little structural damage at Marathon City because most of the land in the floodplain was agriculture. The Rib Falls gage is located six river miles upstream from Marathon City and was operated from 1925-1957.

The principal flood problem in the City of Wausau is on the south side of town, west of the Wisconsin River and south of East Thomas Street. This area is relatively low and mostly occupied by single-family residences. The greatest flood of record occurred on September 1, 1941, which exceeded the July 24, 1912 flood, which was the highest since 1881. The recurrence interval of the 1941 flood is estimated to about one in 170 years, and that of the 1912 flood to about once in 100 years.

The 1912 flood on the Wisconsin River reached a higher stage than the 1941 flood below the Rothschild Dam because a cofferdam was dynamited to save the main structure. The water rushing from Lake Wausau produced a stage at the downstream side of the dam 1.5 feet higher than that of 1941. The flood discharge in the study reach below the dam would also have been higher during the 1912 flood. Effects of cofferdam failures that occurred upstream from Wausau during the 1912 and 1941 floods on the Wisconsin River are unknown.

Other high flood stages have occurred due to backwater from ice jams. Reportedly, thick ice cover on Lake Wausau in the City of Wausau can catch and accumulate ice coming down the river in early spring, sometimes creating considerable backwater. During the spring of 1973, such a jam backed up the river to nearly the 1-percent annual chance flood stage. Another reported outstanding ice jam under the low

railroad bridge over the West Channel of the Wisconsin River, just upstream from the Wausau Dam, caused extensive backwater.

In the City of Wausau, a culvert at a foot crossing in the American Legion Golf Course, approximately 1,900 feet upstream on Jim Moore Creek, is inadequate for passage of even low magnitude flood flows. It can cause approximately 2.5 feet more backwater on floods of the 10-year recurrence interval and greater.

The Wausau Dam on the Wisconsin River can discharge the 0.2-percent annual chance flood at normal pool elevation at the dam. However, there will be a large increase in stage from the dam to Barker's Island, 0.3 mile upstream, during major floods. The principal cause of this increased flood stage is the presence of a former falls in this reach, now submerged from view by the pool created by the dam. Other causes of high flood stages include the horizontal constriction of the flood flows due to control structures under the Memorial Bridge; further constriction is caused by an adjacent island, as well as the width of the West Channel of the Wisconsin River.

Logs reportedly jammed the Rothschild Dam during the 1941 flood, backing up water approximately 1.7 feet higher than for unobstructed conditions.

2.4 Flood Protection Measures

In Marathon County, more than 750 ponds have been constructed by landowners. The Soil Conservation Service (SCS) has assisted in the design and construction of more than half of these small ponds, with more than 250 having some built-in flood control.

For the Village of Athens, there are no flood protection structures on Black Creek or Potato Creek. There are remnants of an old dam on Black Creek which consist of rip-rap and concrete across the stream. This structure does not have sufficient reservoir capacity for significant reduction of flood peaks or volume.

In the City of Wausau, a minimal amount of flood protection exists. A levee just south of the sewage treatment plant offers some protection from flooding, but has gaps in it. Two dams in the area (The American Can Company Dam in Rothschild and the Wausau Dam in Wausau) are used to control discharge as a means of flood protection. As discussed previously, high flood stages do occur upstream from the Wausau Dam.

Both the Domtar Paper Company levee in the Village of Rothschild, and the City of Mosinee Wastewater Treatment Plant levee were shown to provide protection from the Wisconsin River base flood on previous FIRMs. During this study, it was determined that these levees may not meet the operation and maintenance requirements of Title 44 of the Code of Federal Regulations, Section 65.10 for certification under the NFIP. Therefore, for the purpose of this study, these levees were assumed to be ineffective.

3.0 ENGINEERING METHODS

For the flooding sources studied by detailed methods in the community, standard hydrologic and hydraulic study methods were used to determine the flood-hazard data required for this study. Flood events of a magnitude that is expected to be equaled or exceeded once on the average during any 10-, 50-, 100-, or 500-year period (recurrence interval) have been selected as having special significance for floodplain management and for flood insurance rates. These events, commonly termed the 10-, 50-, 100-, and 500-year floods, have a 10-, 2-, 1-, and 0.2-percent chance, respectively, of being equaled or exceeded during any year. Although the recurrence interval represents the long-term, average period between floods of a specific magnitude, rare floods could occur at short intervals or even within the same year. The risk of experiencing a rare flood increases when periods greater than 1 year are considered. For example, the risk of having a flood that equals or exceeds the 1-percent-annual-chance flood in any 50-year period is approximately 40 percent (4 in 10); for any 90-year period, the risk increases to approximately 60 percent (6 in 10). The analyses reported herein reflect flooding potentials based on conditions existing in the community at the time of completion of this study. Maps and flood elevations will be amended periodically to reflect future changes.

3.1 Hydrologic Analyses

Hydrologic analyses were carried out to establish peak discharge-frequency relationships for each flooding source studied by detailed methods affecting the community.

The City of Athens, the villages of Athens and Marathon City, and the unincorporated areas of Marathon County have a previously printed FIS report. The hydrologic analyses described in those reports have been compiled and summarized below.

The following hydrologic analyses have not changed from the previous countywide FIS.

The hydrologic analyses for the unincorporated areas of Marathon County on the Wisconsin River near the City of Mosinee were taken from the Mosinee, Wisconsin Flood Insurance Study (Reference 3). For the Wisconsin River in central Marathon County, peak discharges for floods of 10-, 2-, and 1-percent annual chance recurrence intervals were based on data previously developed for the WDNR by the USGS (Reference 4).

For the Big Rib River and Eau Claire River in unincorporated Marathon County, flood frequency data were based on statistical analysis of stage-discharge records from gaging stations operated by the USGS. The Big Rib River gage at Rib Falls (Gage No. 05396000) has 33 years of record and the Eau Claire River gage (Gage No. 05397500) at Kelly has 52 years of record. These analyses followed the standard log-Pearson Type III method as outlined by the U.S. Water Resources Council

(WRC) (Reference 5). These discharge-frequency relationships were transformed to other locations on the river using a drainage area discharge analysis.

Peak discharges for the Little Rib River, Bull Junior Creek, and Johnson Creek in unincorporated Marathon County were computed using regional flood frequency equations (Reference 6) and compared to a log-Pearson Type III analysis of the Big Rib River at Rib Falls. Discharges for the 0.2- percent annual chance flood of all streams studied in detail in unincorporated Marathon County were determined by straight-line extrapolation of the calculated frequency curves on log-probability paper. The decrease in discharge going downstream Bull Junior Creek in the unincorporated areas of Marathon County is the result of water overtopping the roads near the intersection of U.S. Highway 51 and Kowalski Road. This water leaves the stream, following other paths to the Wisconsin River.

In the Village of Athens, values for the 10-, 2-, and 1-percent flood discharges at the eastern corporate limit and Degner Street for Black Creek were calculated using regional equations developed by Conger (Reference 6). The Conger method employs the following independent variables in a multiple-regression analysis: drainage area, main channel slope, lake and marsh area, main channel length, forest cover, soil index, precipitation intensity, and areal factors. The 0.2-percent flood discharges were defined by extension of the calculated frequency curve on a log-probability plot. Discharge values for the 10- and 2-percent discharges at the confluence with Black Creek for Potato Creek were calculated using the same regional equations (Reference 6). The 1- and 0.2 percent flood discharges were defined by extension of the calculated frequency curve on a log probability plot. The calculated discharges for Black Creek and Potato Creek correlated well with analyses of gage station data on other streams nearby.

In the Village of Athens, gage stations near the Black Creek include the New Wood River gage near Merrill with a record from 1952 to 1975; the Prairie River gage near Merrill with a record from 1921 to 1975; the Big Sandy Creek gage near Wausau with a record from 1963 to 1975; and the Big Eau Pleine gage near Colby with a record from 1962 to 1975. Gage stations near Potato Creek include the Bull Junior Creek gage near Rothschild with a record from 1967 to 1975; and the Pet Brook gage near Edgar with a record from 1961 to 1975. The gage data were made in accordance with the U.S. Water Resources Council Bulletin No. 17 (Reference 7).

In the Village of Marathon City, data from the USGS stream flow gaging station (no. 05-3960.00) located on the Big Rib River at Rib Falls were used in a log-Pearson Type III statistical analysis (Reference 7). The statistical analysis of the observed annual peak discharge values provided estimates of the 10-, 2-, 1-, and 0.2-percent peak flood discharges. These were transferred to the downstream corporate limit and to State Highway 107 in Marathon City by a drainage-area ratio method. The discharge values were coordinated with the Marathon County FIS (Reference 8).

For the City of Wausau, flood-frequency discharges for the Wisconsin River at Rothschild and at Merrill were based on a study of all the stream flow gaging stations on the Wisconsin River by the USACE and the USGS. The flood frequency


discharges for the Wisconsin River at Merrill were multiplied by the drainage area ratio between Wausau and Merrill to determine the corresponding discharges in Wausau upstream from the River. Merrill is about thirteen river miles upstream of Wausau.

In the City of Wausau, flood-frequency data available for the Wisconsin River at Rothschild, the Rib River at Rib Falls, and the Eau Claire River at Kelly were used to determine the flood-frequency discharges in Wausau for the Wisconsin River just downstream from the Rib River. A comparison of the peak discharges at these gaging stations with peak discharges of record in Wisconsin and other states is presented in Figure 1. The peak discharges recorded in Wisconsin are lower than those shown for other states for similar size drainage areas. The Wisconsin flood peaks plotted have recurrence intervals ranging from about 25 years to somewhat greater than 100 years. All flood peaks shown for other states, however, are for outstanding floods. Therefore, it is logical that most of the Wisconsin data points plot lower than the out-of-state data. In central Wisconsin, much greater peak discharges have occurred on the Rib River at Rib Falls than on the Eau Claire River at Kelly, although the drainage areas are nearly the same. This is primarily due to marked differences in basin characteristics. The Rib River drains an area underlain by impermeable crystalline rock overlain by thin glacial drift. The Eau Claire River, on the other hand, drains an area underlain by thick, extensive, and permeable glacial outwash (Reference 9).

In the City of Wausau, flood-frequency curves for the Eau Claire River at Kelly were developed from data in a report by Conger (Reference 6). Flood-frequency data for the Eau Claire River at the dam in Schofield were taken from Gannon (Reference 10).

A flood-frequency curve was computed in the City of Wausau for the Jim Moore Creek at the mouth of the Wisconsin River using a regional analysis (Reference 6). Flood discharges may be lower downstream from the golf course culvert than upstream because storage capacity in the backwater areas temporarily holds some of the floodwaters. Storage analyses were not made, however, in the computation of the flood-frequency discharges used in this study for Jim Moore Creek.

The City of Wausau Dam complex was analyzed using various methods in an attempt to develop a stage-discharge relationship that would fit available historic data near Barker's Island. These data were flood stages with peak discharges of about 23,000 cfs (May 1973) and 50,000 cfs (September 1941). The final method used was based on work compiled by Matthai (Reference 11). The basic equation in Matthai's report includes a discharge coefficient that was adjusted for this study to get the computed data to fit the historical data. A slope conveyance rating at Barker's Island also fits these historical data, but was concave down when plotted graphically, whereas the previous rating was concave up. The relationship based on Matthai was considered to be the better of the two.



F
I
G
U
R
E

1

FEDERAL EMERGENCY MANAGEMENT AGENCY
**MARATHON COUNTY, WI (AND
 INCORPORATED AREAS)**

FREQUENCY – DISCHARGE, DRAINAGE AREA CURVES

WISCONSIN RIVER, RIB RIVER, AND EAU CLAIRE RIVER

Flow rates for the Wisconsin River from the Dam at Mosinee to the Dam at Rothschild were updated to match data included in a 1980 USGS study (Reference 12). The 10-, 2-, and 0.2-percent flows match the unregulated annual maximum flows for gaging station 05398000 at Rothschild. The 1-percent flow represents the regulated annual maximum flow at the Rothschild gage.

A summary of the drainage area-peak discharge relationships for all of the streams studied by detailed methods is shown in Table 5, “Summary of Discharges”.

Table 5 – Summary of Discharges

<u>Flooding Source and Location</u>	<u>Drainage Area</u> (sq. miles)	<u>Peak Discharges (cubic feet per second)</u>			
		<u>10-PERCENT ANNUAL CHANCE</u>	<u>2-PERCENT ANNUAL CHANCE</u>	<u>1-PERCENT ANNUAL CHANCE</u>	<u>0.2-PERCENT ANNUAL CHANCE</u>
BIG RIB RIVER					
At confluence with Wisconsin River	489	22,400	35,600	41,600	54,600
Just upstream from Little Rib River	404	19,750	31,450	36,750	48,200
At Chicago and North Western railroad bridge	386	19,200	30,550	35,700	46,800
Just upstream from Artus Creek	372	18,750	29,800	34,850	45,700
At State Highway 107 at Marathon City	365	18,500	29,450	34,400	45,150
BLACK CREEK					
At east corporate limit of Athens	52.5	3,020	5,000	5,950	8,450
At Degner Street in Athens	40.5	2,400	4,050	4,820	7,000
BULL JUNIOR CREEK					
At confluence with Wisconsin River	37	940	1,590	1,940	2,790
At Adar Road	30	790	1,370	1,640	2,390
At County Highway X	27	950	1,530	1,800	2,550
At Town Road	15	930	1,500	1,750	2,450
EAU CLAIRE RIVER					
At Chicago, Milwaukee, St. Paul & Pacific Railroad bridge at Schofield corporate limit	454	8,100	11,000	12,000	15,000
Just west of County Highway SS, at USGS Gaging Station at Kelly	375	6,500	8,960	9,900	12,000

Table 5 – Summary of Discharges (Continued)

<u>Flooding Source and Location</u>	<u>Drainage Area</u> (sq. miles)	<u>Peak Discharges (cubic feet per second)</u>			
		<u>10-PERCENT ANNUAL CHANCE</u>	<u>2-PERCENT ANNUAL CHANCE</u>	<u>1-PERCENT ANNUAL CHANCE</u>	<u>0.2-PERCENT ANNUAL CHANCE</u>
JOHNSON CREEK					
At County Highway C	29	1,500	2,400	2,850	3,950
At County Highway X	25	1,400	2,200	2,600	3,600
2,900 feet east and 300 feet north of the intersection of Locker Road and County Highway X	21	1,200	1,900	2,250	3,100
3,250 feet east and 5,050 feet north of the intersection of Locker Road and County Highway X	17	1,000	1,600	1,900	2,600
At State Highway 153	12	730	1,150	1,350	1,850
LITTLE RIB RIVER					
At confluence with Big Rib River	80.1	6,600	12,050	15,150	24,000
POTATO CREEK					
At confluence with Black Creek	11.8	1,100	1,850	2,200	3,100
WISCONSIN RIVER					
At Rothschild	4,000	49,000	63,000	64,000	80,000
Just upstream of Eau Claire River	3,590	42,000	61,800	71,100	94,100
At Washington Street in Wausau		18,125 ¹ / 8,325 ²	29,000 ¹ / 91,102 ²	34,680 ¹ / 99,202 ²	47,224 ¹ / 139,002 ²
Just upstream of Big Rib River	3,100	25,600	37,900	44,600	61,300

¹West Channel ²East Channel

3.2 Hydraulic Analyses

Analyses of the hydraulic characteristics of flooding from the sources studied were carried out to provide estimates of the elevations of floods of the selected recurrence intervals. Users should be aware that flood elevations shown on the FIRM represent rounded whole-foot elevations and may not exactly reflect the elevations shown on the Flood Profiles or in the Floodway Data tables in the FIS report. Flood elevations shown on the FIRM are primarily intended for flood insurance rating purposes. For construction and/or floodplain management purposes, users are cautioned to use the flood elevation data presented in this FIS in conjunction with the data shown on the FIRM.

This Physical Map Revision

The hydraulic analysis for the 2015 Lake Wausau Physical Map Revision featured revised floodway limits based on new terrain data provided by Marathon County and entered into a revised HEC-RAS model. There were no updates done to the geometry of the cross sections in the hydraulic model, only a revision to the ineffective flow limits.

Initial Countywide Analyses

Within the unincorporated areas of Marathon County, the Big Rib River and the Wisconsin River were found to have similar discharges at their confluence and have historically flooded simultaneously. Starting water surface elevations for the Big Rib River were taken from established flood profiles on the Wisconsin River (Reference 4). The step-backwater analysis for the 10-, 2-, 1-, and 0.2-percent flood profiles on the Little Rib River were started from the 10-percent flood elevation on the Big Rib River.

On the Eau Claire River within unincorporated Marathon County, starting water-surface elevations (WSEL) were computed by standard procedures for computation of flow over dams (Reference 13). Starting WSELs for the Wisconsin River were computed by a rating curve at a downstream cross section. Starting WSEL for Bull Junior Creek and Johnson Creek were obtained by using a slope-area method. Water surface elevations of floods of the selected recurrence intervals were computed through use of the USGS E431 step-backwater computer program (Reference 14).

Within unincorporated Marathon County, the hydraulic analyses for the Wisconsin River near the City of Mosinee were taken from the Mosinee, Wisconsin Flood Insurance Study (Reference 3). However, no profiles were presented in the Mosinee FIS and therefore none can be presented in this study for the Wisconsin River near Mosinee.

Bull Junior Creek in unincorporated Marathon County was found to cause shallow flooding around the intersection of U.S. Highway 51 and Kowalski Road. After Bull Junior Creek floodwaters rise high enough to overtop the roads, the water that remains trapped behind the roads may flow either north or south depending on the flooding situation in the area. Depths from one to three feet can be expected.

In unincorporated Marathon County, sections of the Big Eau Pleine River, Eau Claire River, Rib River, Elm River, Big Sandy Creek, Norrie Creek, Dill Creek, South Branch Embarrass River, Comet Creek, Spanges Creek, Little Eau Pleine River, Plover River, upper and lower reaches of the Wisconsin River, lower reaches of Johnson Creek, Trappe River, Little Trappe River, Cain Creek, Little Cain Creek, Camp Creek, Prospect Creek, the 100-year flood elevation was approximated by using Flood-Prone Area Maps (Reference 15). For Black Creek, Beaver Creek, West Fork Rib River, Potato Creek, and Drewek Creek, the 1-percent flood elevation was approximated by aerial photographs (Reference 16).

Cross section data for Black Creek and Potato Creek in the Village of Athens were obtained from field surveys by the USGS. The source of starting water-surface elevations for the Black Creek was obtained by a slope-conveyance rating downstream from the Athens corporate limits. Starting water-surface elevations for the Potato Creek were obtained by a critical depth elevation at initial cross sections. Profiles of the 10-, 2-, 1-, and 0.2-percent floods on Black Creek and Potato Creek were computed by the standard step-backwater method using the USGS E431 computer program (Reference 14). Input to these analyses consisted of stream valley cross sections, bridge and culvert geometry, surface roughness, and peak-discharge data. The analysis for the elevation of the portion of Potato Creek studied by approximate methods included interpretation of aerial photographs (Reference 17), field observations, and best engineering judgment.

The starting water-surface elevations for the Big Rib River in the Village of Marathon City were obtained from the Marathon County FIS (Reference 8). Profiles for the 10-, 2-, 1-, and 0.2-percent floods on the Big Rib River at Marathon City were also computed by the standard step-backwater method using the USGS E431 model (Reference 14). Input to the above analyses consisted of stream valley cross sections, bridge geometry, surface roughness, and peak discharge data.

Flood-frequency profiles in the City of Wausau on the Wisconsin River below the Wausau Dam were computed using step-backwater analysis. The starting elevations were taken from Krug and Grant (Reference 18). The computed profiles compare favorably and historic data for the 1941 flood. Above the Wausau Dam complex, at the Memorial Bridge, the starting elevations of flood profiles were determined on work based on Matthai (Reference 11). The Eau Claire River flood profiles in the City were taken from a previous study by Krug and Grant (Reference 18).

The starting elevations for the flood-frequency profiles for Jim Moore Creek in the City of Wausau were based on a slope-conveyance rating at the downstream side of Tenth Street. The slope used was that computed from the stage and discharge for a flood in September of 1972. Data on flood frequency discharges for the Tenth Street Bridge were obtained from the flood-frequency curves included in a Flood Report by the USGS. The 1-percent discharge at this bridge, having a drainage area of approximately 7.32 square miles, was determined to be 3,720 cfs from the above flood-frequency curve.

The Wisconsin River from the Dam at Mosinee to the Dam at Rothschild was updated using a 1991 HEC-2 model completed by the USGS. Model includes updated flow rates as discussed in the Hydrologic section. The HEC-2 model was not only an update from the effective E431 model for this portion of the Wisconsin River, but also included additional surveyed cross sections at key points developed by the USACE.

The effective 1979 USGS Step Backwater Program results were used to extend the Eau Claire River profile to its mouth within the Eau Claire Flowage.

Roughness factors (Manning's "n" values) used in the hydraulic computations were

chosen by engineering judgment and were based on field observations of the streams and floodplain areas. Roughness factors for all streams studied by detailed methods are shown in Table 6, "Manning's "n" Values."

TABLE 6 – MANNING'S "n" VALUE

<u>Stream</u>	<u>Channel "n"</u>	<u>Overbank "n"</u>
Black Creek	0.035 – 0.065	0.055 – 0.110
Bull Junior Creek	0.040 – 0.045	0.050 – 0.120
Eau Claire River	0.035 – 0.050	0.050 – 0.150
Johnson Creek	0.040 – 0.055	0.060 – 0.150
Little Rib River	0.032 – 0.055	0.045 – 0.150
Potato Creek	0.035	0.065 – 0.110
Wisconsin River	0.026 – 0.050	0.050 – 0.110

Locations of selected cross sections used in the hydraulic analyses are shown on the Flood Profiles (Exhibit 1). For stream segments for which a floodway was computed (Section 4.2), selected cross-section locations are also shown on the FIRM (Exhibit 2).

The hydraulic analyses for this study were based on unobstructed flow. The flood elevations shown on the Flood Profiles (Exhibit 1) are thus considered valid only if hydraulic structures remain unobstructed, operate properly, and do not fail.

3.3 Vertical Datum

All FIS reports and FIRMs are referenced to a specific vertical datum. The vertical datum provides a starting point against which flood, ground, and structure elevations can be referenced and compared. Until recently, the standard vertical datum used for newly created or revised FIS reports and FIRMs was the National Geodetic Vertical Datum of 1929 (NGVD29). With the completion of the North American Vertical Datum of 1988 (NAVD88), many FIS reports and FIRMs are now prepared using NAVD88 as the referenced vertical datum.

Flood elevations shown in this FIS report and on the FIRM are referenced to the NAVD88. These flood elevations must be compared to structure and ground elevations referenced to the same vertical datum. Some of the data used in this revision were taken from the prior effective FIS reports and FIRMs and adjusted to NAVD88. The datum conversion factor from NGVD29 to NAVD88 in Marathon County is 0.0 feet.

For additional information regarding conversion between the NGVD29 and NAVD88, visit the National Geodetic Survey website at www.ngs.noaa.gov, or contact the National Geodetic Survey at the following address:

Vertical Network Branch, N/CG13
National Geodetic Survey, NOAA
Silver Spring Metro Center 3
1315 East-West Highway
Silver Spring, Maryland 20910
(301) 713-3191

Temporary vertical monuments are often established during the preparation of a flood hazard analysis for the purpose of establishing local vertical control. Although these monuments are not shown on the FIRM, they may be found in the Technical Support Data Notebook associated with the FIS report and FIRM for this community.

Interested individuals may contact FEMA to access these data.

To obtain current elevation, description, and/or location information for benchmarks shown on this map, please contact the Information Services Branch of the NGS at (301) 713-3242, or visit their website at www.ngs.noaa.gov.

4.0 **FLOODPLAIN MANAGEMENT APPLICATIONS**

The NFIP encourages State and local governments to adopt sound floodplain management programs. To assist in this endeavor, each FIS provides 1-percent annual chance floodplain data, which may include a combination of the following: 10-, 2-, 1-, and 0.2-percent annual chance flood elevations; delineations of the 1-percent annual chance and 0.2-percent annual chance floodplains; and 1-percent annual chance floodway. This information is presented on the FIRM and in many components of the FIS, including Flood Profiles, Floodway Data tables, and Summary of Stillwater Elevation tables. Users should reference the data presented in the FIS as well as additional information that may be available at the local community map repository before making flood elevation and/or floodplain boundary determinations.

4.1 Floodplain Boundaries

To provide a national standard without regional discrimination, the 1-percent annual chance (1-percent annual chance) flood has been adopted by FEMA as the base flood for floodplain management purposes. The 0.2-percent-annual-chance flood is employed to indicate additional areas of flood risk in the community. For each stream studied by detailed methods, the 1- and 0.2-percent-annual-chance floodplain boundaries have been delineated using the flood elevations determined at each cross section.

On the Wisconsin River between lettered cross sections S and AN, boundaries were interpolated using topographic maps at a scale of 1:1200 with a contour interval of 2.0 feet.

For all areas not revised by this study, the boundaries between cross sections within the unincorporated areas of Marathon County were interpolated using 7.5-minute

series topographic maps at a scale of 1:24000, with a contour interval of 10 feet (Reference 19), and 15-Minute Series topographic maps at a scale of 1:62500 with a contour interval of 10 feet (Reference 20).

Between the cross sections within the Village of Athens, boundaries were interpolated using USGS quadrangle maps and aerial photos modified by familiarity with the topography of the valleys (References 17 and 21). The boundary of the floodway was delineated using the left and right flowage limits of the cross sections which, in almost all cases, coincided with the 1-percent annual chance natural valley flood limits. The approximate flood boundaries were delineated using the same topographic maps (Reference 21).

Between the cross sections within the Village of Marathon City, the boundaries were interpolated using topographic maps enlarged to a scale of 1:4800 (Reference 22), aerial photographs (Reference 23), and field inspection.

The 1- and 0.2-percent annual chance floodplain boundaries in the City of Wausau and the Town of Rib Mountain were re-delineated using a digital terrain model that meets the National Map Accuracy Standards for mapping at a scale of 1:1200. Floodplain boundaries were also redelineated in the Village of Weston using 2-foot contours that meet National Map Accuracy Standards for mapping at a scale of 1:2400. Floodplain boundaries in the remainder of the county were digitally converted from the previously effective FIRM.

The 1- and 0.2-percent annual chance floodplain boundaries are shown on the FIRM (Exhibit 2). On this map, the 1-percent annual chance floodplain boundary corresponds to the boundary of the areas of special flood hazards (Zones A and AE), and the 0.2-percent annual chance floodplain boundary corresponds to the boundary of areas of moderate flood hazards. In cases where the 1- and 0.2-percent annual chance floodplain boundaries are close together, only the 1-percent annual chance floodplain boundary has been shown. Small areas within the floodplain boundaries may lie above the flood elevations but cannot be shown due to limitations of the map scale and/or lack of detailed topographic data.

For the streams studied by approximate methods, only the 1-percent-annual-chance floodplain boundary is shown on the FIRM (Exhibit 2).

4.2 Floodways

Encroachment on floodplains, such as structures and fill, reduces flood-carrying capacity, increases flood heights and velocities, and increases flood hazards in areas beyond the encroachment itself. One aspect of floodplain management involves balancing the economic gain from floodplain development against the resulting increase in flood hazard. For purposes of the NFIP, a floodway is used as a tool to assist local communities in this aspect of floodplain management. Under this concept, the area of the 1-percent-annual-chance floodplain is divided into a

floodway and a floodway fringe. The floodway is the channel of a stream, plus any adjacent floodplain areas, that must be kept free of encroachment so that the base flood can be carried without substantial increases in flood heights. Minimum Federal standards limit such increases to 1.0 foot, provided that hazardous velocities are not produced. However, Wisconsin has established a more strict policy and does not allow any increase in the regional flood height for flood fringe developments (Reference 24). The increase shown in Table 7, "Floodway Data" for certain stream segments were calculated before this policy went into effect, and are shown as the regulatory elevation to remain in compliance with the current regulation. The floodways in this FIS are presented to local agencies as minimum standards that can be adopted directly or that can be used as a basis for additional floodway studies.

The floodways presented in the previous study were computed for certain stream segments on the basis of equal conveyance reduction from each side of the floodplain. Floodway widths were computed at cross sections. Between cross sections, the floodway boundaries were interpolated. The results of the floodway computations are tabulated for selected cross sections (see Table 7, "Floodway Data"). The computed floodways are shown on the FIRM (Exhibit 2). In cases where the floodway and 1-percent-annual-chance floodplain boundaries are either close together or collinear, only the floodway boundary is shown.

For the previous countywide study, floodways computed in the 1973 USGS study (Reference 4) for the Wisconsin River, Eau Claire River, and Jim Moore Creek were added.

For the previous countywide study's redelineation efforts, the floodways were not recalculated. As a result, there were areas where the previous floodway did not fit within the boundaries of the redelineated 1-percent annual chance floodplain. In these areas, the floodway was reduced. Water surface elevations, with and without a floodway, the mean velocity in the floodway, and the location and area at each surveyed cross section as determined by the hydraulic methods can be seen in Table 7.

The area between the floodway and 1-percent-annual-chance floodplain boundaries is termed the floodway fringe. The floodway fringe encompasses the portion of the floodplain that could be completely obstructed without increasing the WSEL of the base flood more than 1 foot at any point. Typical relationships between the floodway and the floodway fringe and their significance to floodplain development are shown in Figure 2, "Floodway Schematic."

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
BIG RIB RIVER								
A	2,746	1,932	20,560	2.0	1,167.5	1,167.5	1,167.5	0.0
B	3,854	3,042	29,560	1.4	1,167.6	1,167.6	1,167.6	0.0
C	7,075	3,268	21,960	1.9	1,168.1	1,168.1	1,168.1	0.0
D	7,920	2,533	14,540	2.9	1,168.6	1,168.6	1,168.6	0.0
E	10,138	1,955	13,880	3.0	1,169.9	1,169.9	1,169.9	0.0
F	12,038	2,415	18,035	2.3	1,171.0	1,171.0	1,171.0	0.0
G	15,048	3,435	19,860	1.9	1,172.4	1,172.4	1,172.4	0.0
H	20,909	2,144	19,150	1.9	1,174.2	1,174.2	1,174.2	0.0
I	22,651	2,088	16,820	2.2	1,175.2	1,175.2	1,175.2	0.0
J	24,130	3,177	23,630	1.6	1,176.5	1,176.5	1,176.5	0.0
K	24,922	3,141	21,510	1.7	1,176.8	1,176.8	1,176.8	0.0
L	27,350	3,450	24,480	1.5	1,177.9	1,177.9	1,177.9	0.0
M	29,040	3,890	21,040	1.8	1,178.8	1,178.8	1,178.8	0.0
N	30,835	3,757	29,260	1.3	1,179.5	1,179.5	1,179.5	0.0
O	33,528	3,323	25,190	1.5	1,180.3	1,180.3	1,180.3	0.0
P	34,637	3,700	22,420	1.6	1,181.0	1,181.0	1,181.0	0.0
Q	36,960	1,979	14,110	2.6	1,182.3	1,182.3	1,182.3	0.0
R	37,910	2,998	16,170	2.3	1,182.7	1,182.7	1,182.7	0.0
S	39,811	2,722	21,930	1.7	1,184.7	1,184.7	1,184.7	0.0
T	41,078	2,772	22,910	1.6	1,185.3	1,185.3	1,185.3	0.0
U	42,346	2,820	21,400	1.7	1,185.9	1,185.9	1,185.9	0.0
V	43,243	2,012	16,360	2.3	1,186.4	1,186.4	1,186.4	0.0
W	44,141	1,450	12,340	2.9	1,187.2	1,187.2	1,187.2	0.0
X	44,669	604	6,280	5.7	1,187.5	1,187.5	1,187.5	0.0
Y	45,619	863	8,990	4.0	1,188.5	1,188.5	1,188.5	0.0

¹FEET ABOVE CONFLUENCE WITH WISCONSIN RIVER

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
**MARATHON COUNTY, WI
AND INCORPORATED AREAS**

FLOODWAY DATA

BIG RIB RIVER

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
BIG RIB RIVER (CONTINUED)								
Z	46,253	916	8,240	4.3	1,189.5	1,189.5	1,189.5	0.0
AA	47,045	1,231	10,750	3.3	1,190.6	1,190.6	1,190.6	0.0
AB	47,942	1,289	11,570	3.1	1,191.0	1,191.0	1,191.0	0.0
AC	48,998	1,650	15,760	2.3	1,191.7	1,191.7	1,191.7	0.0
AD	49,843	2,427	20,620	1.7	1,192.2	1,192.2	1,192.2	0.0
AE	50,688	2,415	17,890	2.0	1,192.7	1,192.7	1,192.7	0.0
AF	51,586	2,006	21,230	1.7	1,193.3	1,193.3	1,193.3	0.0
AG	52,483	2,501	21,580	1.7	1,193.7	1,193.7	1,193.7	0.0
AH	53,222	2,629	28,050	1.3	1,194.2	1,194.2	1,194.2	0.0
AI	54,490	1,517	13,280	2.7	1,194.4	1,194.4	1,194.4	0.0
AJ	55,282	1,668	21,410	1.7	1,194.9	1,194.9	1,194.9	0.0
AK	55,915	1,916	20,560	1.7	1,195.0	1,195.0	1,195.0	0.0
AL	56,813	2,111	13,660	2.6	1,195.3	1,195.3	1,195.3	0.0
AM	57,710	2,550	27,570	1.3	1,196.1	1,196.1	1,196.1	0.0
AN	59,875	3,054	28,250	1.2	1,196.2	1,196.2	1,196.2	0.0
AO	60,720	2,647	13,930	2.5	1,196.2	1,196.2	1,196.2	0.0
AP	61,459	1,821	8,200	4.3	1,196.5	1,196.5	1,196.5	0.0
AQ	62,357	1,515	10,410	3.4	1,197.1	1,197.1	1,197.1	0.0
AR	64,310	2,499	12,720	2.7	1,198.7	1,198.7	1,198.7	0.0
AS	64,786	2,224	13,710	2.5	1,199.9	1,199.9	1,199.9	0.0
AT	66,211	1,643	10,390	3.4	1,201.1	1,201.1	1,201.1	0.0
AU	67,267	1,699	11,000	3.2	1,202.3	1,202.3	1,202.3	0.0
AV	68,218	1,900	11,770	3.0	1,202.8	1,202.8	1,202.8	0.0
AW	72,547	2,080	20,700	1.7	1,203.8	1,203.8	1,203.8	0.0

¹FEET ABOVE CONFLUENCE WITH WISCONSIN RIVER

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS

FLOODWAY DATA

BIG RIB RIVER

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
BIG RIB RIVER (CONTINUED)								
AX	73,709 ¹	1,870	14,500	2.4	1,204.0	1,204.0	1,204.0	0.0
AY	74,501 ¹	960	10,600	3.2	1,204.3	1,204.3	1,204.3	0.0
AZ	75,134 ¹	860	9,500	3.6	1,204.5	1,204.5	1,204.5	0.0
BA	76,085 ¹	1,570	11,300	3.1	1,205.0	1,205.0	1,205.0	0.0
BB	78,302 ¹	1,610	14,600	2.4	1,205.7	1,205.7	1,205.7	0.0
BC	80,995 ¹	1,443	12,710	2.7	1,206.7	1,206.7	1,206.7	0.0
BD	82,685 ¹	797	7,260	4.7	1,208.2	1,208.2	1,208.2	0.0
BLACK CREEK								
A	40,392 ²	275	916	6.5	1,313.2	1,313.2	1,313.2	0.0
B	40,814 ²	340	1,280	4.7	1,315.4	1,315.4	1,315.4	0.0
C	41,184 ²	190	945	6.3	1,316.2	1,316.2	1,316.2	0.0
D	41,976 ²	220	981	4.9	1,318.5	1,318.5	1,318.5	0.0
E	42,451 ²	260	1,020	4.7	1,320.7	1,320.7	1,320.7	0.0
F	42,874 ²	390	888	5.4	1,322.4	1,322.4	1,322.4	0.0
G	43,296 ²	140	802	6.0	1,324.2	1,324.2	1,324.2	0.0
H	43,507 ²	200	1,260	3.9	1,327.3	1,327.3	1,327.3	0.0
I	43,824 ²	370	1,710	2.8	1,327.8	1,327.8	1,327.8	0.0
J	44,246 ²	130	731	6.6	1,328.0	1,328.0	1,328.0	0.0
K	44,669 ²	130	812	5.9	1,330.1	1,330.1	1,330.1	0.0
L	45,038 ²	160	961	5.0	1,331.6	1,331.6	1,331.6	0.0
M	45,355 ²	90	428	11.3	1,335.2	1,335.2	1,335.2	0.0
N	45,619 ²	170	1,120	4.3	1,339.9	1,339.9	1,339.9	0.0
O	45,936 ²	100	472	10.2	1,341.6	1,341.6	1,341.6	0.0

¹FEET ABOVE CONFLUENCE WITH WISCONSIN RIVER, ²FEET ABOVE CONFLUENCE WITH BIG RIB RIVER

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS

FLOODWAY DATA

BIG RIB RIVER - BLACK CREEK

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
BLACK CREEK (CONTINUED)								
P	46,200 ¹	110	509	9.5	1,348.2	1,348.2	1,348.2	0.0
Q	46,886 ¹	130	619	7.8	1,353.7	1,353.7	1,353.7	0.0
R	47,678 ¹	170	1,050	4.6	1,358.2	1,358.2	1,358.2	0.0
S	47,890 ¹	240	1,460	3.3	1,361.4	1,361.4	1,361.4	0.0
T	49,421 ¹	450	2,360	2.1	1,362.8	1,362.8	1,362.8	0.0
BULL JUNIOR CREEK								
A	637 ²	149	315	6.2	1,146.7	1,141.3 ³	1,141.3	0.0
B	845 ²	350	955	2.0	1,146.7	1,142.9 ³	1,142.9	0.0
C	1,056 ²	300	875	2.2	1,146.7	1,143.1 ³	1,143.1	0.0
D	1,848 ²	208	715	2.7	1,146.7	1,144.1 ³	1,144.1	0.0
E	2534 ²	160	465	4.2	1,146.7	1,146.3 ³	1,146.3	0.0
F	3,168 ²	233	775	2.5	1,148.0	1,148.0	1,148.0	0.0
G	3,590 ²	121	285	6.8	1,148.7	1,148.7	1,148.7	0.0
H	4,013 ²	134	565	3.4	1,151.4	1,151.4	1,151.4	0.0
I	4,118 ²	81	560	3.5	1,152.8	1,152.8	1,152.8	0.0
J	4,171 ²	94	380	5.1	1,152.8	1,152.8	1,152.8	0.0
K	5,016 ²	434	1,905	1.0	1,153.6	1,153.6	1,153.6	0.0
L	5,914 ²	278	1,190	1.6	1,153.8	1,153.8	1,153.8	0.0
M	6,706 ²	233	850	2.3	1,154.2	1,154.2	1,154.2	0.0
N	6,917 ²	114	495	3.9	1,154.3	1,154.3	1,154.3	0.0
O	7,709 ²	171	620	3.1	1,155.4	1,155.4	1,155.4	0.0
P	8,448 ²	183	685	2.8	1,156.2	1,156.2	1,156.2	0.0
Q	9,293 ²	344	1,275	1.5	1,157.2	1,157.2	1,157.2	0.0

¹FEET ABOVE CONFLUENCE WITH BIG RIB RIVER, ²FEET ABOVE MOUTH AT WISCONSIN RIVER, ³ELEVATION COMPUTED WITHOUT CONSIDERATION OF BACKWATER EFFECTS FROM WISCONSIN RIVER

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS

FLOODWAY DATA

BLACK CREEK - BULL JUNIOR CREEK

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
BULL JUNIOR CREEK (CONTINUED)								
R	10,402	919	2,305	0.8	1,157.8	1,157.8	1,157.8	0.0
S	12,619	784	2,190	0.9	1,158.7	1,158.7	1,158.7	0.0
T	14,256	429	725	2.7	1,160.8	1,160.8	1,160.8	0.0
U	14,362	530	1,104	1.8	1,161.2	1,161.2	1,161.2	0.0
V	15,734	427	88	2.2	1,162.4	1,162.4	1,162.4	0.0
W	16,579	324	1,000	2.0	1,163.4	1,163.4	1,163.4	0.0
X	18,110	391	1,115	1.7	1,164.6	1,164.6	1,164.6	0.0
Y	19,166	640	1,400	1.4	1,165.6	1,165.6	1,165.6	0.0
Z	20,381	474	1,305	1.5	1,166.6	1,166.6	1,166.6	0.0
AA	21,278	885	2,140	0.9	1,167.2	1,167.2	1,167.2	0.0
AB	22,704	563	1,185	1.6	1,168.3	1,168.3	1,168.3	0.0
AC	23,496	695	1,795	1.1	1,168.9	1,168.9	1,168.9	0.0
AD	24,552	728	1,660	1.2	1,169.4	1,169.4	1,169.4	0.0
AE	25,450	720	2,650	0.7	1,169.8	1,169.8	1,169.8	0.0
AF	27,086	886	1,365	1.4	1,170.3	1,170.3	1,170.3	0.0
AG	28,248	230	455	3.6	1,172.8	1,172.8	1,172.8	0.0
AH	28,406	662	1,845	0.8	1,173.6	1,173.6	1,173.6	0.0
AI	29,410	631	1,480	1.1	1,173.8	1,173.8	1,173.8	0.0
AJ	30,466	1,110	1,185	1.4	1,174.7	1,174.7	1,174.7	0.0
AK	31,574	1,011	2,240	0.2	1,175.8	1,175.8	1,175.8	0.0
AL	32,472	773	1,415	1.2	1,176.1	1,176.1	1,176.1	0.0
AM	33,000	579	1,300	1.4	1,176.7	1,176.7	1,176.7	0.0
AN	33,581	584	1,285	1.4	1,177.4	1,177.4	1,177.4	0.0
AO	34,531	749	2,000	0.9	1,178.3	1,178.3	1,178.3	0.0

¹FEET ABOVE MOUTH AT WISCONSIN RIVER

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
**MARATHON COUNTY, WI
AND INCORPORATED AREAS**

FLOODWAY DATA

BULL JUNIOR CREEK

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
BULL JUNIOR CREEK (CONTINUED)								
AP	35,957	802	2,370	0.8	1,178.6	1,178.6	1,178.6	0.0
AQ	37,013	671	1,665	1.1	1,179.4	1,179.4	1,179.4	0.0
AR	38,491	821	2,230	0.8	1,180.3	1,180.3	1,180.3	0.0
AS	39,811	728	1,840	1.0	1,181.0	1,181.0	1,181.0	0.0
AT	41,237	736	1,785	1.0	1,181.6	1,181.6	1,181.6	0.0
AU	42,821	852	1,290	1.4	1,183.3	1,183.3	1,183.3	0.0
AV	43,666	514	1,855	1.0	1,184.1	1,184.1	1,184.1	0.0
AW	44,774	562	1,685	1.1	1,184.4	1,184.4	1,184.4	0.0
AX	45,408	582	1,635	1.1	1,184.8	1,184.8	1,184.8	0.0
AY	45,514	454	1,485	1.2	1,185.7	1,185.7	1,185.7	0.0
AZ	46,517	532	1,575	1.1	1,186.1	1,186.1	1,186.1	0.0
BA	47,784	312	800	2.2	1,187.1	1,187.1	1,187.1	0.0
BB	49,104	643	1,630	1.1	1,189.0	1,189.0	1,189.0	0.0
BC	50,054	533	1,520	1.2	1,189.9	1,189.9	1,189.9	0.0
BD	51,269	443	1,200	1.5	1,191.2	1,191.2	1,191.2	0.0
BE	52,272	490	1,175	1.5	1,192.3	1,192.3	1,192.3	0.0
BF	53,170	297	885	2.0	1,193.5	1,193.5	1,193.5	0.0
BG	54,120	206	580	1.9	1,194.4	1,194.4	1,194.4	0.0
BH	55,440	361	1,215	0.9	1,194.9	1,194.9	1,194.9	0.0
EAU CLAIRE RIVER								
A	7,339	336	2,055	5.8	1,169.6	1,169.6	1,169.6	0.0
B	8,501	372	2,442	4.9	1,171.3	1,171.3	1,171.3	0.0
C	9,451	722	3,696	3.2	1,172.1	1,172.1	1,172.1	0.0

¹FEET ABOVE MOUTH AT WISCONSIN RIVER

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS

FLOODWAY DATA

BULL JUNIOR CREEK - EAU CLAIRE RIVER

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
EAU CLAIRE RIVER (CONTINUED)								
D	12,619	1,371	7,045	1.7	1,173.5	1,173.5	1,173.5	0.0
E	13,570	655	3,520	3.4	1,174.2	1,174.2	1,174.2	0.0
F	14,098	713	3,198	3.7	1,174.4	1,174.4	1,174.4	0.0
G	16,262	1,162	5,073	2.4	1,175.4	1,175.4	1,175.4	0.0
H	17,107	1,408	5,902	2.0	1,176.6	1,176.6	1,176.6	0.0
I	20,856	691	3,589	3.3	1,178.5	1,178.5	1,178.5	0.0
J	21,173	374	2,709	4.4	1,178.9	1,178.9	1,178.9	0.0
K	21,384	422	2,862	4.2	1,179.1	1,179.1	1,179.1	0.0
L	22,598	955	6,649	1.8	1,179.8	1,179.8	1,179.8	0.0
M	27,298	1,645	6,056	1.6	1,180.9	1,180.9	1,180.9	0.0
N	29,410	1,247	6,310	1.6	1,182.1	1,182.1	1,182.1	0.0
O	31,363	1,118	4,270	2.3	1,183.2	1,183.2	1,183.2	0.0
P	33,106	566	2,436	4.1	1,185.3	1,185.3	1,185.3	0.0
Q	34,003	239	1,569	6.3	1,186.8	1,186.8	1,186.8	0.0
R	35,218	285	1,846	5.4	1,189.1	1,189.1	1,189.1	0.0
S	35,429	175	1,764	5.6	1,189.3	1,189.3	1,189.3	0.0
T	36,643	228	1,651	6.0	1,191.0	1,191.0	1,191.0	0.0
U	38,122	720	4,036	2.4	1,193.2	1,193.2	1,193.2	0.0
V	39,019	837	4,381	2.3	1,193.9	1,193.9	1,193.9	0.0
W	40,022	1,174	4,560	2.2	1,194.8	1,194.8	1,194.8	0.0
X	41,870	1,319	6,556	1.6	1,197.0	1,197.0	1,197.0	0.0
Y	43,085	1,126	5,963	1.7	1,197.4	1,197.4	1,197.4	0.0
Z	45,091	205	1,265	7.8	1,199.7	1,199.7	1,199.7	0.0
AA	46,517	355	2,470	4.0	1,202.6	1,202.6	1,202.6	0.0

¹FEET ABOVE MOUTH AT WISCONSIN RIVER

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
**MARATHON COUNTY, WI
AND INCORPORATED AREAS**

FLOODWAY DATA

EAU CLAIRE RIVER

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
EAU CLAIRE RIVER (CONTINUED)								
AB	47,731	422	3,003	3.3	1,203.8	1,203.8	1,203.8	0.0
AC	48,946	644	3,409	2.9	1,204.8	1,204.8	1,204.8	0.0
AD	49,790	381	2,566	3.9	1,205.3	1,205.3	1,205.3	0.0
AE	51,322	226	1,616	6.1	1,207.3	1,207.3	1,207.3	0.0
AF	52,958	341	1,363	7.3	1,212.9	1,212.9	1,212.9	0.0
AG	53,170	355	1,932	5.1	1,214.0	1,214.0	1,214.0	0.0
AH	54,226	534	2,950	3.4	1,216.4	1,216.4	1,216.4	0.0
AI	55,176	1,013	5,000	2.0	1,217.7	1,217.7	1,217.7	0.0
AJ	56,760	1,547	4,350	2.3	1,219.5	1,219.5	1,219.5	0.0
AK	58,766	447	2,730	3.6	1,222.0	1,222.0	1,222.0	0.0
AL	60,245	554	1,800	5.5	1,223.9	1,223.9	1,223.9	0.0
AM	62,146	1,513	6,350	1.6	1,226.6	1,226.6	1,226.6	0.0
AN	63,518	1,290	6,230	1.6	1,227.3	1,227.3	1,227.3	0.0
AO	64,838	1,043	4,440	2.2	1,228.3	1,228.3	1,228.3	0.0
AP	66,581	1,254	5,920	1.7	1,229.3	1,229.3	1,229.3	0.0
AQ	69,802	981	3,510	2.8	1,231.2	1,231.2	1,231.2	0.0
AR	71,438	803	3,440	2.9	1,233.9	1,233.9	1,233.9	0.0
AS	72,706	1,381	7,520	1.3	1,235.4	1,235.4	1,235.4	0.0
AT	73,814	498	2,510	3.9	1,236.0	1,236.0	1,236.0	0.0
AU	74,184	467	2,900	3.4	1,237.0	1,237.0	1,237.0	0.0
AV	75,240	937	3,860	2.6	1,237.6	1,237.6	1,237.6	0.0
AW	77,088	734	3,350	3.0	1,239.5	1,239.5	1,239.5	0.0
AX	77,986	788	3,630	2.7	1,240.1	1,240.1	1,240.1	0.0
AY	79,306	931	6,140	1.6	1,240.6	1,240.6	1,240.6	0.0

¹FEET ABOVE MOUTH AT WISCONSIN RIVER

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
**MARATHON COUNTY, WI
AND INCORPORATED AREAS**

FLOODWAY DATA

EAU CLAIRE RIVER

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
EAU CLAIRE RIVER (CONTINUED)								
AZ	81,206 ¹	1,012	5,830	1.7	1,241.1	1,241.1	1,241.1	0.0
BA	82,579 ¹	553	3,480	2.8	1,241.9	1,241.9	1,241.9	0.0
BB	83,635 ¹	526	2,960	3.4	1,243.0	1,243.0	1,243.0	0.0
BC	84,427 ¹	558	2,700	3.7	1,243.8	1,243.8	1,243.8	0.0
BD	85,694 ¹	630	3,360	2.9	1,245.1	1,245.1	1,245.1	0.0
BE	87,014 ¹	339	2,680	3.7	1,246.0	1,246.0	1,246.0	0.0
BF	88,546 ¹	313	2,030	4.9	1,247.2	1,247.2	1,247.2	0.0
BG	89,549 ¹	545	3,890	2.6	1,248.2	1,248.2	1,248.2	0.0
BH	90,816 ¹	642	3,080	3.2	1,248.7	1,248.7	1,248.7	0.0
BI	91,925 ¹	561	3,030	3.3	1,249.6	1,249.6	1,249.6	0.0
BJ	92,189 ¹	277	2,040	4.9	1,249.7	1,249.7	1,249.7	0.0
JIM MOORE CREEK A-K								
	*	*	*	*	*	*	*	*
JOHNSON CREEK								
A	18,427 ²	770	3,710	0.8	1,127.7	1,127.7	1,127.7	0.0
B	19,589 ²	754	3,350	0.9	1,127.8	1,127.8	1,127.8	0.0
C	20,486 ²	330	1,210	2.4	1,127.9	1,127.9	1,127.9	0.0
D	22,070 ²	351	1,050	2.7	1,129.5	1,129.5	1,129.5	0.0
E	22,968 ²	613	1,970	1.5	1,130.5	1,130.5	1,130.5	0.0
F	24,922 ²	342	1,320	2.2	1,131.2	1,131.2	1,131.2	0.0
G	25,714 ²	277	960	3.0	1,131.9	1,131.9	1,131.9	0.0
H	27,720 ²	446	910	3.1	1,135.1	1,135.1	1,135.1	0.0

¹FEET ABOVE MOUTH AT WISCONSIN RIVER, ²FEET ABOVE MOUTH AT LAKE DU BAY, *DATA NOT AVAILABLE

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS

FLOODWAY DATA

EAU CLAIRE RIVER - JIM MOORE CREEK - JOHNSON CREEK

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
JOHNSON CREEK (CONTINUED)								
I J	27,826	543	2,640	1.1	1,140.0	1,140.0	1,140.0	0.0
K	28,406	556	3,420	0.8	1,140.1	1,140.1	1,140.1	0.0
L	29,779	454	2,400	1.2	1,140.3	1,140.3	1,140.3	0.0
M	30,677	673	3,890	0.7	1,140.5	1,140.5	1,140.5	0.0
N	31,627	704	2,300	1.2	1,140.6	1,140.6	1,140.6	0.0
O	32,630	177	850	3.4	1,141.2	1,141.2	1,141.2	0.0
P	34,056	263	1,040	2.7	1,142.9	1,142.9	1,142.9	0.0
Q	35,323	597	2,540	1.0	1,143.7	1,143.7	1,143.7	0.0
R	35,640	644	2,230	1.2	1,146.3	1,146.3	1,146.3	0.0
S	36,854	696	1,000	2.6	1,146.7	1,146.7	1,146.7	0.0
T	38,227	840	1,850	1.4	1,148.6	1,148.6	1,148.6	0.0
U	39,178	667	1,400	1.9	1,149.8	1,149.8	1,149.8	0.0
V	40,392	536	1,390	1.9	1,151.8	1,151.8	1,151.8	0.0
W	41,712	613	1,300	1.7	1,154.0	1,154.0	1,154.0	0.0
X	43,349	104	340	6.6	1,157.4	1,157.4	1,157.4	0.0
Y	44,616	629	3,040	0.7	1,160.0	1,160.0	1,160.0	0.0
Z	46,042	299	640	3.5	1,160.5	1,160.5	1,160.5	0.0
AA	47,256	563	1,080	2.1	1,163.4	1,163.4	1,163.4	0.0
AB	48,206	298	810	2.8	1,165.4	1,165.4	1,165.4	0.0
AC	49,157	435	1,000	1.9	1,167.0	1,167.0	1,167.0	0.0
AD	49,843	413	920	2.1	1,167.8	1,167.8	1,167.8	0.0
AE	50,635	447	720	2.6	1,169.7	1,169.7	1,169.7	0.0
AF	51,902	432	1,270	1.5	1,171.2	1,171.2	1,171.2	0.0
	53,222	185	430	4.5	1,173.1	1,173.1	1,173.1	0.0

¹FEET ABOVE MOUTH AT LAKE DU BAY

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
**MARATHON COUNTY, WI
AND INCORPORATED AREAS**

FLOODWAY DATA

JOHNSON CREEK

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
JOHNSON CREEK (CONTINUED) AG								
AH	54,331 ¹	294	1,170	1.6	1,175.7	1,175.7	1,175.7	0.0
AI	56,021 ¹	49	220	8.8	1,178.1	1,178.1	1,178.1	0.0
AJ	56,179 ¹	680	1,900	1.0	1,180.4	1,180.4	1,180.4	0.0
AK	57,288 ¹	752	650	2.9	1,181.2	1,181.2	1,181.2	0.0
AL	58,186 ¹	203	480	3.9	1,183.8	1,183.8	1,183.8	0.0
AM	59,770 ¹	129	390	4.8	1,187.1	1,187.1	1,187.1	0.0
AN	59,928 ¹	282	1,320	1.4	1,191.1	1,191.1	1,191.1	0.0
AO	61,406 ¹	242	720	2.6	1,191.9	1,191.9	1,191.9	0.0
AP	62,462 ¹	179	640	3.0	1,193.0	1,193.0	1,193.0	0.0
AQ	63,466 ¹	228	580	3.3	1,195.0	1,195.0	1,195.0	0.0
AR	64,258 ¹	258	510	2.7	1,198.4	1,198.4	1,198.4	0.0
AS	65,314 ¹	76	220	6.3	1,201.9	1,201.9	1,201.9	0.0
AT	66,634 ¹	250	610	2.2	1,206.1	1,206.1	1,206.1	0.0
	67,267 ¹	161	340	4.0	1,208.1	1,208.1	1,208.1	0.0
LITTLE RIB RIVER								
A								
B	4,910 ²	856	6,190	2.4	1,173.7	1,173.7	1,173.7	0.0
C	5,386 ²	1,000	6,360	2.3	1,174.6	1,174.6	1,174.6	0.0
D	5,966 ²	804	6,036	2.5	1,175.3	1,175.3	1,175.3	0.0
E	6,230 ²	594	5,696	2.7	1,175.5	1,175.5	1,175.5	0.0
F	6,917 ²	500	5,524	2.7	1,176.1	1,176.1	1,176.1	0.0
G	7,234 ²	180	1,690	9.0	1,176.2	1,176.2	1,176.2	0.0
H	7,392 ²	146	1,687	9.0	1,176.2	1,176.2	1,176.2	0.0
	7,814 ²	157	1,482	10.2	1,178.3	1,178.3	1,178.3	0.0

¹FEET ABOVE MOUTH AT LAKE DU BAY, ²FEET ABOVE CONFLUENCE WITH BIG RIB RIVER

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
 AND INCORPORATED AREAS

FLOODWAY DATA

JOHNSON CREEK - LITTLE RIB RIVER

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
LITTLE RIB RIVER								
I	7,867 ¹	715	8,530	1.8	1,181.2	1,181.2	1,181.2	0.0
J	9,082 ¹	1,092	12,713	1.2	1,181.6	1,181.6	1,181.6	0.0
K	9,926 ¹	1,104	13,290	1.1	1,181.8	1,181.8	1,181.8	0.0
L	10,560 ¹	1,249	14,004	1.1	1,181.9	1,181.9	1,181.9	0.0
M	11,458 ¹	850	8,423	1.8	1,182.4	1,182.4	1,182.4	0.0
POTATO CREEK								
A	370 ²	50	205	10.8	1,317.9	1,314.9 ³	1,314.9	0.0
B	528 ²	240	416	5.3	1,319.3	1,319.3	1,319.3	0.0
C	845 ²	240	446	4.9	1,320.5	1,320.5	1,320.5	0.0
D	950 ²	150	589	3.7	1,323.0	1,323.0	1,323.0	0.0
E	1,267 ²	215	528	4.2	1,323.4	1,323.4	1,323.4	0.0
F	1,531 ²	200	696	3.2	1,324.9	1,324.9	1,324.9	0.0
G	1,901 ²	200	704	3.1	1,325.5	1,325.5	1,325.5	0.0
H	2,218 ²	120	377	5.8	1,325.9	1,325.9	1,325.9	0.0
WISCONSIN RIVER								
A	268.63 ⁴	3,538	23,529	5.1	1,146.7	1,146.7	1,146.7	0.0
B	269.31 ⁴	2,492	20,388	5.9	1,147.9	1,147.9	1,147.9	0.0
C	279.73 ⁴	1,976	16,357	5.8	1,148.6	1,148.6	1,148.6	0.0
D	270.15 ⁴	1,372	16,235	5.9	1,149.3	1,149.3	1,149.3	0.0
E	270.78 ⁴	1,631	16,481	6.2	1,150.5	1,150.5	1,150.5	0.0
F	271.27 ⁴	898	11,465	6.5	1,151.4	1,151.4	1,151.4	0.0
G	271.90 ⁴	1,100	11,411	7.1	1,152.7	1,152.7	1,152.7	0.0
H	272.43 ⁴	925	11,610	6.8	1,153.8	1,153.8	1,153.8	0.0

¹FEET ABOVE CONFLUENCE WITH BIG RIB RIVER, ²FEET ABOVE CONFLUENCE WITH BLACK CREEK, ³ELEVATION COMPUTED WITHOUT CONSIDERATION OF BACKWATER EFFECTS FROM BLACK RIVER, ⁴MILES ABOVE MOUTH AT MISSISSIPPI RIVER

TABLE 7

**FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS**

FLOODWAY DATA

LITTLE RIB RIVER - POTATO CREEK - WISCONSIN RIVER

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
WISCONSIN RIVER (CONTINUED)								
I	273.14	902	13,780	5.1	1,155.1	1,155.1	1,155.1	0.0
J	273.44	577	10,992	5.8	1,155.4	1,155.4	1,155.4	0.0
K	273.46	629	13,652	4.7	1,155.7	1,155.7	1,155.7	0.0
L	273.88	800	11,875	6.5	1,156.0	1,156.0	1,156.0	0.0
M	274.22	686	11,154	6.1	1,156.6	1,156.6	1,156.6	0.0
N	274.67	557	10,241	6.6	1,157.2	1,157.2	1,157.2	0.0
O	274.87	502	10,093	6.3	1,157.6	1,157.6	1,157.6	0.0
P	275.11	473	10,372	6.2	1,158.0	1,158.0	1,158.0	0.0
Q	275.28	509	11,353	5.6	1,158.3	1,158.3	1,158.3	0.0
R	275.44	786	31,882	2.1	1,158.8	1,158.8	1,158.8	0.0
S	275.51	883	22,908	3.5	1,164.1	1,164.1	1,164.1	0.0
T	275.89	650	15,751	4.8	1,164.2	1,164.2	1,164.2	0.0
U	275.96	861	18,518	4.1	1,164.4	1,164.4	1,164.4	0.0
V	276.34	2,142	36,632	2.1	1,164.7	1,164.7	1,164.7	0.0
W	276.53	2,284	33,986	2.2	1,164.7	1,164.7	1,164.7	0.0
X	276.95	3,665	59,223	1.3	1,164.9	1,164.9	1,164.9	0.0
Y	277.42	3,427	28,925	2.5	1,164.9	1,164.9	1,164.9	0.0
Z	277.83	751	13,694	5.2	1,165.0	1,165.0	1,165.0	0.0
AA	278.03	1,955	30,631	2.3	1,165.6	1,165.6	1,165.6	0.0
AB	278.47	2,902	37,672	1.9	1,165.9	1,165.9	1,165.9	0.0
AC	278.96	1,851	18,448	2.4	1,166.0	1,166.0	1,166.0	0.0
AD	279.32	1,022	17,509	2.5	1,166.1	1,166.1	1,166.1	0.0
AE	279.53	2,504	34,487	1.3	1,166.3	1,166.3	1,166.3	0.0
AF	279.91	2,686	29,388	1.5	1,166.4	1,166.4	1,166.4	0.0

¹MILES ABOVE MOUTH AT MISSISSIPPI RIVER

TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS

FLOODWAY DATA

WISCONSIN RIVER

FLOODING SOURCE		FLOODWAY			1-PERCENT-ANNUAL-CHANCE FLOOD WATER SURFACE ELEVATION (FEET NAVD 88)			
CROSS SECTION	DISTANCE ¹	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	REGULATORY	WITHOUT FLOODWAY	WITH FLOODWAY	INCREASE
WISCONSIN RIVER (CONTINUED)								
AG	280.17	1,471	17,846	2.5	1,166.5	1,166.5	1,166.5	0.0
AH	280.71	966	12,624	3.5	1,166.9	1,166.9	1,166.9	0.0
AI	280.92	1,082	12,352	3.6	1,167.2	1,167.2	1,167.2	0.0
AJ	281.24	643	9,104	4.9	1,167.9	1,167.9	1,167.9	0.0
AK	281.36	642	11,656	3.8	1,168.3	1,168.3	1,168.3	0.0
AL	281.58	1,543	10,406	4.3	1,168.5	1,168.5	1,168.5	0.0
AM	281.77	1,320	11,139	4.0	1,169.3	1,169.3	1,169.3	0.0
AN	281.96	1,472	12,251	3.6	1,169.8	1,169.8	1,169.8	0.0
AO-AX	*	*	*	*	*	*	*	*


TABLE 7

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS

FLOODWAY DATA

WISCONSIN RIVER

FIGURE 2 – FLOODWAY SCHEMATIC



5.0 INSURANCE APPLICATION

For flood insurance rating purposes, flood insurance zone designations are assigned to a community based on the results of the engineering analyses. The zones are as follows:

Zone A

Zone A is the flood insurance rate zone that corresponds to the 1-percent floodplains that are determined in the FIS by approximate methods. Because detailed hydraulic analyses are not performed for such areas, no base (1-percent annual chance) flood elevations or depths are shown within this zone.

Zone AE

Zone AE is the flood insurance rate zone that corresponds to the 1-percent annual chance floodplains that are determined in the FIS by detailed methods. In most instances, whole-foot base flood elevations derived from the detailed hydraulic analyses are shown at selected intervals within this zone.

Zone AO

Zone AO is the flood insurance rate zone that corresponds to areas of 1-percent-annual-chance shallow flooding (usually sheet flow on sloping terrain) where

average depths are between 1 and 3 feet. Average whole-foot depths derived from the detailed hydraulic analyses are shown within this zone.

Zone X

Zone X is the flood insurance rate zone that corresponds to areas outside the 0.2-percent annual chance floodplain, areas within the 0.2-percent annual chance floodplain, and to areas of 1-percent annual chance flooding where average depths are less than 1 foot, areas of 1-percent annual chance flooding where the contributing drainage area is less than 1 square mile, and areas protected from the 1-percent annual chance flood by levees. No base flood elevations or depths are shown within this zone.

6.0 **FLOOD INSURANCE RATE MAP**

The FIRM is designed for flood insurance and floodplain management applications.

For flood insurance applications, the map designates flood insurance rate zones as described in Section 5.0 and, in the 1-percent-annual-chance floodplains that were studied by detailed methods, shows selected whole-foot base flood elevations or average depths. Insurance agents use zones and base flood elevations in conjunction with information on structures and their contents to assign premium rates for flood insurance policies.

For floodplain management applications, the map shows by tints, screens, and symbols, the 1- and 0.2-percent-annual-chance floodplains. Floodways and the locations of selected cross sections used in the hydraulic analyses and floodway computations are shown where applicable.

The countywide FIRM presents flooding information for the entire geographic area of Marathon County. Previously, FIRMs were prepared for each incorporated community and the unincorporated areas of the County identified as flood-prone. This countywide FIRM also includes flood-hazard information that was presented separately on Flood Boundary and Floodway Maps (FBFMs), where applicable. Historical data relating to the maps prepared for each community are presented in Table 8, "Community Map History."

COMMUNITY NAME	INITIAL IDENTIFICATION	FLOOD HAZARD BOUNDARY MAP REVISION DATE(S)	FLOOD INSURANCE RATE MAP EFFECTIVE DATE	FLOOD INSURANCE RATE MAP REVISION DATE(S)
Abbotsford, City of (Dual County Community) (Clark County)	July 22, 2010	None	July 22, 2010	None
Athens, Village of	May 31, 1974	May 14, 1976	August 15, 1980	None
¹ Birnamwood, Village of (Dual County Community) (Shawano County)	May 31, 1974	May 14, 1976	August 19, 1985	None
Brokaw, Village of	December 17, 1973	May 21, 1976	June 1, 1988	None
Colby, City of (Dual County Community) (Clark County)	May 31, 1974	March 19, 1976 March 23, 1979	September 18, 1985	None
¹ Dorchester, Village of (Dual County Community) (Clark County)	N/A December 3,	None	N/A September 30,	None
Edgar, Village of	1976	None	1988	None
Elderon, Village of	July 19, 1974	July 30, 1976	July 22, 2010	None
Fenwood, Village of	August 2, 1974	May 14, 1976	July 22, 2010	None
Hatley, Village of	July 19, 1974	May 14, 1976	September 27, 1985	None

¹No Special Flood Hazard Areas identified

TABLE 8	FEDERAL EMERGENCY MANAGEMENT AGENCY MARATHON COUNTY, WI AND INCORPORATED AREAS	COMMUNITY MAP HISTORY
----------------	---	------------------------------

COMMUNITY NAME	INITIAL IDENTIFICATION	FLOOD HAZARD BOUNDARY MAP REVISION DATE(S)	FLOOD INSURANCE RATE MAP EFFECTIVE DATE	FLOOD INSURANCE RATE MAP REVISION DATE(S)
Kronenwetter, Village of	August 3, 1981 ¹	None	August 3, 1981 ¹	None
Marathon City, Village of	November 30, 1973	May 21, 1976	August 15, 1980	None
Marathon County (Unincorporated Areas)	February 1, 1979	None	February 1, 1979	August 3, 1981
² Marshfield, City of (Dual County Community) Wood County	February 17, 2010 ³	None	February 17, 2010 ³	None
Mosinee, City of	December 16, 1973	None	December 16, 1973	July 1, 1974 November 14, 1975
Rothschild, Village of	May 11, 1973	None	May 11, 1973	July 1, 1974 May 21, 1976 January 21, 1977 March 31, 1978
Schofield, City of	July 13, 1973	None	July 13, 1973	July 1, 1974 March 12, 1976 February 8, 1980
⁴ Spencer, Village of	N/A	None	N/A	None

¹Formerly shown on the Marathon County (Unincorporated Areas) Flood Insurance Rate Map ²No Special Flood Hazard Areas identified within Marathon County

³Wood County and Incorporated Areas Flood Insurance Rate Map ⁴No Special Flood Hazard Areas identified

TABLE 8	FEDERAL EMERGENCY MANAGEMENT AGENCY	COMMUNITY MAP HISTORY
	MARATHON COUNTY, WI AND INCORPORATED AREAS	

COMMUNITY NAME	INITIAL IDENTIFICATION	FLOOD HAZARD BOUNDARY MAP REVISION DATE(S)	FLOOD INSURANCE RATE MAP EFFECTIVE DATE	FLOOD INSURANCE RATE MAP REVISION DATE(S)
Stratford, Village of	December 17, 1973	May 21, 1976	May 1, 1987	None
¹ Unity, Village of (Dual County Community) (Clark County)	September 20, 1974	June 4, 1976	July 6, 2010 ²	None
Wausau, City of	January 5, 1978	None	January 5, 1978	None
Weston, Village of	August 3, 1981 ³	None	August 3, 1981 ³	None

¹No Special Flood Hazard Areas identified within Marathon County ²Clark County and Incorporated Areas Flood Insurance Rate Map

³Formerly shown on the Marathon County (Unincorporated Areas) Flood Insurance Rate Map

TABLE 8	FEDERAL EMERGENCY MANAGEMENT AGENCY MARATHON COUNTY, WI AND INCORPORATED AREAS	COMMUNITY MAP HISTORY
----------------	---	------------------------------

7.0 OTHER STUDIES

This FIS report either supersedes or is compatible with all previous studies published on streams studied in this report and should be considered authoritative for the purposes of the NFIP.

The countywide studies for Clark, Lincoln, Portage, and Wood counties in Wisconsin are in progress and might impact the information presented in this countywide FIS report.

8.0 LOCATION OF DATA

Information concerning the pertinent data used in preparation of this FIS can be obtained by contacting Federal Insurance and Mitigation Division, FEMA Region V, 536 South Clark Street, Sixth Floor, Chicago, Illinois 60605.

9.0 BIBLIOGRAPHY AND REFERENCES

1. U.S. Department of Commerce, Bureau of the Census. (1990, 2000). Census of Population, Wisconsin, Washington, D.C.
2. Village Clerk, Oral Communications, Village of Athens, Wisconsin.
3. U.S. Department of Housing and Urban Development, Flood Insurance Administration. (1975). Flood Insurance Study, City of Mosinee, Wisconsin.
4. U.S. Geological Survey. (1973). Flood Plain and Floodway Delineation for Regional Flood in Central Marathon County, Wisconsin. Madison, Wisconsin.
5. U.S. Water Resources Council, Bulletin No. 17A. (1977). Guidelines for Determining Flood Flow Frequency.
6. D. H. Conger. (1971). Estimating Magnitude and Frequency of Floods in Wisconsin. U.S. Geological Survey, Open-File Report.
7. U.S. Water Resources Council, Bulletin No. 17. (1976). Guidelines for Determining Flood Flow Frequency.
8. U.S. Department of Housing and Urban Development, Federal Insurance Administration. (1979). Flood Insurance Study, Marathon County, Unincorporated Areas, Wisconsin.
9. E.A. Bell and M.G. Sherrill. (1971). Water Availability in Central Wisconsin – An Area of Near Surface Crystalline Rock. U.S. Geological Survey, Open-File Report.
10. W.G. Gannon. (1972). Flood Insurance Study of Marathon County, Wisconsin. Unpublished report.

11. H.F. Matthai. (1967). Measurement of Peak Discharge at Width Contractions by Indirect Methods: Techniques of Water Resource Investigations, Book 3, Chapter A3.
12. U.S. Department of the Interior, Geological Survey. (1980). Streamflow of Wisconsin River for Estimating Flood Frequency and Volume. Water Resource Investigations, Open File Report, 80-1103.
13. H. Hulsing. (1967). Measurement of Peak Discharge at Dams by Indirect Methods. U.S. Geological Survey, Open-File Report.
14. J.O. Shearman. (1976). Computer Applications for Step-Backwater and Floodway Analysis. U.S. Geological Survey, Open-File Report 76-499.
15. U.S. Geological Survey, Flood-Prone Area Maps, 15-and 7.5-Minutes Series, Scales of 1:24000, Contour Intervals 10 feet: Merrill Quadrangle, Wisconsin (1969); Abbotsford Quadrangle, Wisconsin (1974); Stratford Quadrangle, Wisconsin (1973); Marathon Quadrangle, Wisconsin (1973); Wausau West Quadrangle, Wisconsin (1969); Wausau East Quadrangle, Wisconsin (1969); Wausau Quadrangle, Wisconsin (1969); Hatley Quadrangle, Wisconsin (1973); Granton Quadrangle, Wisconsin (1974); Marshfield Quadrangle, Wisconsin (1973); Honey Island Quadrangle, Wisconsin (1973); Big Eau Pleine Reservoir Quadrangle, Wisconsin (1973); Dancy Quadrangle, Wisconsin (1973); Rosholt N.W. Quadrangle, Wisconsin (1973).
16. U.S. Geological Survey, Marathon County, Wisconsin. (1974). Aerial Coverage, Hamburg and Athens Quadrangle, GS-VCZG.
17. U.S. Department of Agriculture, Soil Conservation Service. (1968). Aerial Photographs: Athens, Wisconsin.
18. W.R. Krug and R.S. Grant. (1973). Flood Insurance Study of Schofield, Wisconsin. U.S. Geological Survey, Open-File Report.
19. U.S. Geological Survey, 7.5-Minute Series Maps: Scale 1:24000, Contour Interval of 10 feet: Wausau West, Wisconsin (1969); Wausau East, Wisconsin (1969); Honey Island, Wisconsin (1973); Big Eau Pleine Reservoir, Wisconsin (1973); Dancy, Wisconsin (1973); Marsh, Wisconsin (1970); Rosholt N. W., Wisconsin (1969); Rosholt (1969); Tigerton N.W., Wisconsin (1970).
20. U.S. Geological Survey, 15-Minute Series Flood-Prone Area Maps, Scale 1:62500, Contour Interval of 10 feet: Athens, Wisconsin (1951); Hamburg, Wisconsin (1951); Merrill, Wisconsin (1969); Doering, Wisconsin (1951); Antigo, Wisconsin (1952); Abbotsford, Wisconsin (1974); Stratford, Wisconsin (1973); Marathon, Wisconsin (1973); Hatley, Wisconsin (1973); Wittenberg, Wisconsin (1974); Marshfield, Wisconsin (1973); Granton, Wisconsin (1974); Wausau, Wisconsin (1969).

21. U.S. Geological Survey. (1951). 15 Minute Series Topographic Maps, Athens Quadrangle, Wisconsin. Scale 1:62500, Contour Interval of 20 feet.
22. U.S. Geological Survey. (1963). Topographic Quadrangle Map, Marathon, Wisconsin. Scale 1:62500, Contour Interval of 20 feet.
23. U.S. Department of Agriculture, Soil Conservation Service. (1968). Aerial Photographs: Village of Marathon City, Wisconsin.
24. Wisconsin Department of Natural Resources. (2004). Wisconsin's Floodplain Management Program. Chapter NR116, Register No. 584.
25. L. Martin. (1932). The Physical Geography of Wisconsin. Wisconsin Geological and Natural History Survey.
26. U.S. Department of Commerce, National Oceanic and Atmospheric Administration, (1973). Monthly Normals of Temperature, Precipitation, and Heating and Cooling Degree Days, 1941-70.
27. Hole, F.D. (1976). Soils of Wisconsin. University of Wisconsin Extension, Geological and Natural History Survey.
28. L.M. Andrews and H. Carlson. (1977). Surface Water Resources of Marathon County, Wisconsin. Wisconsin Department of Natural Resources.
29. Wisconsin Department of Administration, Madison, WI. (1977). The State of Wisconsin Blue Book.
30. U.S. Department of Housing and Urban Development, Federal Insurance Administration. (1976). Flood Hazard Boundary Map, Village of Athens, Wisconsin.
31. Wisconsin Department of Administration. (1978). Official Population Estimates for 1978.
32. Wisconsin Department of Natural Resources. (1977). Wisconsin's Flood Plain Management Program, Chapter NR 116, Register No. 259.
33. Wisconsin Department of Natural Resources, Publication No. 3-880 (75). (1975). Natural Resources Use Controls and Assistance.
34. Federal Emergency Management Agency, Flood Insurance Administration. (1980). Flood Insurance Study, Village of Athens, Wisconsin.
35. Federal Emergency Management Agency, Flood Insurance Administration. (1980). Flood Insurance Study, Village of Marathon City, Wisconsin.

36. Federal Emergency Management Agency, Flood Insurance Administration. (1977). Flood Insurance Study, City of Wausau, Wisconsin.
37. Federal Emergency Management Agency, Flood Insurance Administration. (1976). Flood Insurance Study, City of Schofield, Wisconsin.
38. Federal Emergency Management Agency, Flood Insurance Administration. (1983). Flood Insurance Study, Portage County, Wisconsin.
39. Federal Emergency Management Agency, Flood Insurance Administration. (1979). Communication with P. Hughes, Madison, Wisconsin.
40. U.S. Department of Housing and Urban Development, Flood Insurance Administration. (1978). Flood Insurance Study, Village of Rothschild, Wisconsin.
41. Marathon County Planning Commission, Wausau, Wisconsin. Town Maps, Scale 1:24000: Town of Wausau (1979); Town of Weston (1977); Town of Mosinee (1979), Town of Knowlton (1978); Town of Stettin (undated); Town of Kronenwetter (1979); and Town of Rib Mountain (1978).
42. W.R. Krug, R.S. Grant, and M.D. Duerk, (Unpublished report). Flood Plain and Floodway Delineation for Regional Flood in Central Marathon County, Wisconsin. U.S. Geological Survey, Open-File Report.
43. G.L. Bodhaine. (1960). Measurements of Peak Discharge at Culverts by Indirect Methods: Techniques of Water Resources Investigations, Book 3, Chapter A3. , U.S. Geological Survey Open-File Report.
44. U.S. Department of Housing and Urban Development, Federal Insurance Administration. (1973). Flood Hazard Boundary Map, Village of Marathon City, Wisconsin.
45. Becher & Hoppe Engineering, Schofield, Wisconsin. Map of Village of Athens, Wisconsin, Scale 1:6000.
46. Chow, V.T. (1959) Open Channel Hydraulics. New York: McGraw-Hill Book Company, Inc.

10.0 ADDITIONAL INFORMATION

Information concerning the pertinent data used in the preparation of this FIS Report can be obtained by submitting an order with any required payment to the FEMA Engineering Library. For more information on this process, see <http://www.fema.gov>.

10.1 FIRM Notes to Users

Each FIS report provides floodplain data, which may include a combination of the following: 10-, 4-, 2-, 1-, and 0.2-percent-annual-chance flood elevations (the 1-percent-annual-chance flood elevation is also referred to as the Base Flood Elevation (BFE)); delineations of the 1-percent-annual-chance and 0.2-percent-annual-chance floodplains; and 1-percent-annual-chance floodway. This information is presented on the FIRM and/or in many components of the FIS report, including Flood Profiles and Floodway Data tables. Figure 3 presents important considerations for using the information contained in this FIS report and the FIRM and is provided in response to changes in format and content. Figure 4 presents the map legend for the FIRM.

FIGURE 3 - FIRM NOTES TO USERS

NOTES TO USERS

For information and questions about this map, available products associated with this FIRM including historic versions of this FIRM, how to order products, or the National Flood Insurance Program in general, please call the FEMA Map Information eXchange at 1-877-FEMA-MAP (1-877-336-2627) or visit the FEMA Map Service Center website at <http://msc.fema.gov>. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. Many of these products can be ordered or obtained directly from the website. Users may determine the current map date for each FIRM panel by visiting the FEMA Map Service Center website or by calling the FEMA Map Information eXchange.

Communities annexing land on adjacent FIRM panels must obtain a current copy of the adjacent panel as well as the current FIRM Index. These may be ordered directly from the Map Service Center at the number listed above.

For community and countywide map dates, refer to Table 8 in this FIS Report.

To determine if flood insurance is available in the community, contact your insurance agent or call the National Flood Insurance Program at 1-800-638-6620.

The map is for use in administering the NFIP. It may not identify all areas subject to flooding, particularly from local drainage sources of small size. Consult the community map repository to find updated or additional flood hazard information.

BASE FLOOD ELEVATIONS: For more detailed information in areas where Base Flood Elevations (BFEs) and/or floodways have been determined, consult the Flood Profiles and Floodway Data and/or Summary of Stillwater Elevations tables within this FIS Report. Use the flood elevation data within the FIS Report in conjunction with the FIRM for construction and/or floodplain management.

FLOODWAY INFORMATION: Boundaries of the floodways were computed at cross sections and interpolated between cross sections. The floodways were based on hydraulic considerations with regard to requirements of the National Flood Insurance Program. Floodway widths and other pertinent floodway data are provided in the FIS Report for this jurisdiction.

FLOOD CONTROL STRUCTURE INFORMATION: Certain areas not in Special Flood Hazard Areas may be protected by flood control structures. Refer to Section 4.2 "Flood Protection Measures" of this FIS Report for information on flood control structures for this jurisdiction.

PROJECTION INFORMATION: The projection used in the preparation of the map was Universal Transverse Mercator (UTM) Zone 16. The horizontal datum was NAD83_HARN. Differences in datum, spheroid, projection or State Plane zones used in the production of FIRMs for adjacent jurisdictions may result in slight positional differences in map features across jurisdiction boundaries. These differences do not affect the accuracy of the FIRM.

ELEVATION DATUM: Flood elevations on the FIRM are referenced to North American Vertical Datum of 1988. These flood elevations must be compared to structure and ground elevations referenced to the same vertical datum. For information regarding conversion between the National Geodetic Vertical Datum of 1929 and North American Vertical Datum of 1988, visit the National Geodetic Survey website at <http://www.ngs.noaa.gov/> or contact the National Geodetic Survey at the following address:

NGS Information Services
NOAA, N/NGS12
National Geodetic Survey
SSMC-3, #9202
1315 East-West Highway
Silver Spring, Maryland 20910-3282
(301) 713-3242

Local vertical monuments may have been used to create the map. To obtain current monument information, please contact the appropriate local community listed in Table 8 of this FIS Report.

BASE MAP INFORMATION: Base map information shown on the FIRM was provided by multiple sources. Aerial photography for the initial countywide analysis was flown in the Spring of 2005 and provided by Marathon County Conservation, Planning and Zoning Department. Aerial photography for the Lake Wausau Physical Map Revision was flown in the Spring of 2015 and provided by the Wisconsin Regional Orthophotography Consortium (WROC). For information about base maps, refer to Section 1.2 "Authority of Acknowledgements" in this FIS Report.

Corporate limits shown on the map are based on the best data available at the time of publication. Because changes due to annexations or de-annexations may have occurred after the map was published, map users should contact appropriate community officials to verify current corporate limit locations.

NOTES FOR FIRM INDEX

REVISIONS TO INDEX: As new studies are performed and FIRM panels are updated within Marathon County, Wisconsin and Incorporated Areas, corresponding revisions to the FIRM Index will be incorporated within the FIS Report to reflect the effective dates of those panels. Please refer to Table 8 of this FIS Report to determine the most recent FIRM revision date for each community. The most recent FIRM panel effective date will correspond to the most recent index date.

SPECIAL NOTES FOR SPECIFIC FIRM PANELS

This Notes to Users section was created specifically for Marathon County, Wisconsin and Incorporated Areas, effective **TBD**.

FLOOD RISK REPORT: A Flood Risk Report (FRR) may be available for many of the flooding sources and communities referenced in this FIS Report. The FRR is provided to increase public awareness of flood risk by helping communities identify the areas within their jurisdictions that have the greatest risks. Although non-regulatory, the information provided within the FRR can assist communities in assessing and evaluating mitigation opportunities to reduce these risks. It can also be used by communities developing or updating flood risk mitigation plans. These plans allow communities to identify and evaluate opportunities to reduce potential loss of life and property. However, the FRR is not intended to be the final authoritative source of all flood risk data for a project area; rather, it should be used with other data sources to paint a comprehensive picture of flood risk.

Each FIRM panel contains an abbreviated legend for the features shown on the maps. However, the FIRM panel does not contain enough space to show the legend for all map features. Figure 4 shows the full legend of all map features. Note that not all of these features may appear on the FIRM panels in Marathon County.

FIGURE 4 – MAP LEGEND FOR FIRM

SPECIAL FLOOD HAZARD AREAS: *The 1% annual chance flood, also known as the base flood or 100-year flood, has a 1% chance of happening or being exceeded each year. Special Flood Hazard Areas are subject to flooding by the 1% annual chance flood. The Base Flood Elevation is the water-surface elevation of the 1% annual chance flood. The floodway is the channel of a stream plus any adjacent floodplain areas that must be kept free of encroachment so that the 1% annual chance flood can be carried without substantial increases in flood heights. See note for specific types. If the floodway is too narrow to be shown, a note is shown.*



Special Flood Hazard Areas subject to inundation by the 1% annual chance flood (Zones A, AE, AH, AO, AR, A99, V and VE)

- Zone A The flood insurance rate zone that corresponds to the 1% annual chance floodplains. No base (1% annual chance) flood elevations (BFEs) or depths are shown within this zone.
- Zone AE The flood insurance rate zone that corresponds to the 1% annual chance floodplains. Base flood elevations derived from the hydraulic analyses are shown within this zone, either at cross section locations or as static whole-foot elevations that apply throughout the zone.
- Zone AH The flood insurance rate zone that corresponds to the areas of 1% annual chance shallow flooding (usually areas of ponding) where average depths are between 1 and 3 feet. Whole-foot BFEs derived from the hydraulic analyses are shown at selected intervals within this zone.
- Zone AO The flood insurance rate zone that corresponds to the areas of 1% annual chance shallow flooding (usually sheet flow on sloping terrain) where average depths are between 1 and 3 feet. Average whole-foot depths derived from the hydraulic analyses are shown within this zone.
- Zone AR The flood insurance rate zone that corresponds to areas that were formerly protected from the 1% annual chance flood by a flood control system that was subsequently decertified. Zone AR indicates that the former flood control system is being restored to provide protection from the 1% annual chance or greater flood.

Zone A99	The flood insurance rate zone that corresponds to areas of the 1% annual chance floodplain that will be protected by a Federal flood protection system where construction has reached specified statutory milestones. No base flood elevations or flood depths are shown within this zone.
Zone V	The flood insurance rate zone that corresponds to the 1% annual chance coastal floodplains that have additional hazards associated with storm waves. Base flood elevations are not shown within this zone.
Zone VE	Zone VE is the flood insurance rate zone that corresponds to the 1% annual chance coastal floodplains that have additional hazards associated with storm waves. Base flood elevations derived from the coastal analyses are shown within this zone as static whole-foot elevations that apply throughout the zone.
	Regulatory Floodway determined in Zone AE.

OTHER AREAS OF FLOOD HAZARD



Shaded Zone X: Areas of 0.2% annual chance flood hazards and areas of 1% annual chance flood hazards with average depths of less than 1 foot or with drainage areas less than 1 square mile.



Future Conditions 1% Annual Chance Flood Hazard – Zone X: The flood insurance rate zone that corresponds to the 1% annual chance floodplains that are determined based on future-conditions hydrology. No base flood elevations or flood depths are shown within this zone.



Zone X Protected by Accredited Levee: Areas protected by an accredited levee, dike or other flood control structures. See Notes to Users for important information.

OTHER AREAS




Zone D (Areas of Undetermined Flood Hazard): The flood insurance rate zone that corresponds to unstudied areas where flood hazards are undetermined, but possible



Unshaded Zone X: Areas determined to be outside the 0.2% annual chance floodplain

FLOOD HAZARD AND OTHER BOUNDARY LINES



Flood Zone Boundary (white line)



Limit of Study




Jurisdiction Boundary




Limit of Moderate Wave Action (LiMWA): Indicates the inland limit of the area affected by waves greater than 1.5 feet

GENERAL STRUCTURES



Channel, Culvert, Aqueduct, or Storm Sewer



Dam, Jetty, Weir



Levee, Dike or Floodwall accredited or provisionally accredited to provide protection from the 1% annual chance flood



Levee, Dike or Floodwall not accredited to provide protection from the 1% annual chance flood.




Bridge

COASTAL BARRIER RESOURCES SYSTEM (CBRS) AND OTHERWISE PROTECTED AREAS (OPA): *CBRS areas and OPAs are normally located within or adjacent to Special Flood Hazard Areas. See Notes to Users for important information.*



CBRS AREA
09/30/2009

Coastal Barrier Resources System Area: Labels are shown to clarify where this area shares a boundary with an incorporated area or overlaps with the floodway.



OTHERWISE PROTECTED AREA
09/30/2009


Otherwise Protected Area

REFERENCE MARKERS



River mile Markers

CROSS SECTION & TRANSECT INFORMATION



Lettered Cross Section with Regulatory Water Surface Elevation (BFE)



Numbered Cross Section with Regulatory Water Surface Elevation (BFE)




Unlettered Cross Section with Regulatory Water Surface Elevation (BFE)



Coastal Transect


 	<p>Profile Baseline: Indicates the modeled flow path of a stream and is shown on FIRM panels for all valid studies with profiles or otherwise established base flood elevation.</p> <p>Coastal Transect Baseline: Used in the coastal flood hazard model to represent the 0.0-foot elevation contour and the starting point for the transect and the measuring point for the coastal mapping.</p>
 <p>ZONE AE (EL 16)</p> <p>ZONE AO (DEPTH 2)</p> <p>ZONE AO (DEPTH 2) (VEL 15 FPS)</p>	<p>Base Flood Elevation Line (shown for flooding sources for which no cross sections or profile are available)</p> <p>Static Base Flood Elevation value (shown under zone label)</p> <p>Zone designation with Depth</p> <p>Zone designation with Depth and Velocity</p>
<p>BASE MAP FEATURES</p>	
<p><u>Missouri Creek</u></p>	<p>River, Stream or Other Hydrographic Feature</p>
	<p>Interstate Highway</p>
	<p>U.S. Highway</p>
	<p>State Highway</p>
	<p>County Highway</p>
<p><u>MAPLE LANE</u></p>	<p>Street, Road, Avenue Name, or Private Drive if shown on Flood Profile</p>
	<p>Railroad</p>
	<p>Horizontal Reference Grid Line</p>
	<p>Horizontal Reference Grid Ticks</p>
	<p>Secondary Grid Crosshairs</p>
<p>Land Grant</p>	<p>Name of Land Grant</p>
<p>7</p>	<p>Section Number</p>
<p>R. 43 W. T. 22 N.</p>	<p>Range, Township Number</p>
<p>42-76^{000m}E</p>	<p>Horizontal Reference Grid Coordinates (UTM)</p>
<p>365000 FT</p>	<p>Horizontal Reference Grid Coordinates (State Plane)</p>
<p>80° 16' 52.5"</p>	<p>Corner Coordinates (Latitude, Longitude)</p>



FLOOD PROFILES


BIG RIB RIVER

**FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS**



FLOOD PROFILES
BULL JUNIOR CREEK


FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS



FLOOD PROFILES
BULL JUNIOR CREEK

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS

07P




FLOOD PROFILES

BULL JUNIOR CREEK

FEDERAL EMERGENCY MANAGEMENT AGENCY

MARATHON COUNTY, WI

AND INCORPORATED AREAS




FLOOD PROFILES


BULL JUNIOR CREEK

FEDERAL EMERGENCY MANAGEMENT AGENCY

MARATHON COUNTY, WI

AND INCORPORATED AREAS






FLOOD PROFILES


LITTLE RIB RIVER

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
 AND INCORPORATED AREAS



FLOOD PROFILES
WISCONSIN RIVER

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS




FLOOD PROFILES

WISCONSIN RIVER

FEDERAL EMERGENCY MANAGEMENT AGENCY

MARATHON COUNTY, WI
AND INCORPORATED AREAS




FLOOD PROFILES

WISCONSIN RIVER


FEDERAL EMERGENCY MANAGEMENT AGENCY

MARATHON COUNTY, WI
AND INCORPORATED AREAS



FLOOD PROFILES
WISCONSIN RIVER

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS



FLOOD PROFILES
WISCONSIN RIVER

FEDERAL EMERGENCY MANAGEMENT AGENCY
MARATHON COUNTY, WI
AND INCORPORATED AREAS

