

ADDENDUM

Addendum No. 1, February 10, 2020

RE: UWSP – Marathon County
Fieldhouse Plumbing and Pool Piping Rre

FROM: Aquatic Design Solutions, LLC
17921 Fulda Trail
Lakeville, MN 55044

TO: Prospective Bidders

This Addendum forms a part of Bidding Documents dated January 21, 2020. Acknowledge receipt of this Addendum in space provided on Bid Form. Failure to do so may subject Bidder to disqualification.

THIS ADDENDUM CONSISTS OF 1 PAGE, NOT INCLUDING ATTACHMENTS

ATTACHMENTS TO ADDENDUM

1. Pre-Bid Meeting Notes. All changes discussed in meeting notes shall take precedence over original construction documents.
2. Detail 2/PL2.

CHANGES TO CONSTRUCTION DRAWINGS - GENERAL

1. The awarded contractor shall be responsible for engineering/design of the domestic water heating system and submit to state and local as required for permitting. This plan review shall be paid directly by Contractor and included in bid. Contractor is also responsible for all permits required to perform the work. The Owner shall have the pool plans submitted to the state for plan review following the opening of the bids. Contractor shall understand that this plan review will not be completed until approximately mid June, 2020.

CHANGES TO DRAWINGS

1. Sheet PL1:
 - a) Add note, Contractor may salvage existing 2" pool chemical injection loop for reinstallation in new plumbing.
 - b) Add note, Contractor shall salvage sensor in existing 6" line to be reused in the new PVC piping.
2. Sheet PL2:
 - a) Contractor shall provide pool ball valves on all wall inlet lines, typical of 8 locations.
 - b) Add attached Detail 2/PL2 Valve & Flow Meter Schedule to drawing.
 - c) Contractor shall provide one 3 ½" pressure gauge, dial range 0 to 60, stainless steel or aluminum case, liquid filled, Terice or equal, on existing pump discharge side of pump.

- d) Add note: Contractor shall provide concentric reducer fitting between existing pump and new pool strainer.
 - e) Add note, Contractors are allowed to tap the pipe and or fittings to install gauges and chemical connections in pool piping. All locations shall be watertight.
3. Sheet P2:
- a) Add note 6 to plumbing notes: 6. Contractor shall connect existing cold water line to new domestic water heating system with Type L copper piping and provide new piping insulation.

CHANGES TO SPECIFICATIONS

- 1. Section 131700, Article 2.03, Paragraph B, delete and replace with following: B. Signet Flow Meter – For lines sizes 6” and larger, Signet Flow Instrument 3-5090 with 515 Paddlewheel flow sensor with saddle, or approved equal. Flow meter shall be calibrated with pipe size.

END OF ADDENDUM