

ADDENDUM

Addendum No. 2, February 12, 2020

RE: UWSP – Marathon County
Fieldhouse Plumbing and Pool Piping Replacement Project

FROM: Aquatic Design Solutions, LLC
17921 Fulda Trail
Lakeville, MN 55044

TO: Prospective Bidders

This Addendum forms a part of Bidding Documents dated January 21, 2020. Acknowledge receipt of this Addendum in space provided on Bid Form. Failure to do so may subject Bidder to disqualification.

THIS ADDENDUM CONSISTS OF 1 PAGE, NOT INCLUDING ATTACHMENTS

CHANGES TO DRAWINGS

1. Sheet PL2, add the following note: 7. Contractor shall add one horizontal, 6” Hayward WCV Series Full Pattern Wafer Check Valve, PVC, with 316 stainless steel spring and EPDM gasket and disc seal, or equal, to recirculation line following the 6” flow meter. Install downstream of flow meter so not in clearance requirements of flow meter. Provide flanges and galvanized bolt packs for complete installation of check valve.

END OF ADDENDUM